


STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐

APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER NBU 1022-12K1BS							
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT NATURAL BUTTES							
4. TYPE OF WELL Gas Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME NATURAL BUTTES							
6. NAME OF OPERATOR KERR-MCGEE OIL & GAS ONSHORE, L.P.						7. OPERATOR PHONE 720 929-6515							
8. ADDRESS OF OPERATOR P.O. Box 173779, Denver, CO, 80217						9. OPERATOR E-MAIL julie.jacobson@anadarko.com							
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UT ST UO 01997-A ST				11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>				12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>					
13. NAME OF SURFACE OWNER (if box 12 = 'fee')						14. SURFACE OWNER PHONE (if box 12 = 'fee')							
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')							
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')				18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input checked="" type="checkbox"/> (Submit Commingling Application) NO <input type="checkbox"/>				19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>					
20. LOCATION OF WELL		FOOTAGES		QTR-QTR		SECTION		TOWNSHIP		RANGE		MERIDIAN	
LOCATION AT SURFACE		2473 FNL 2359 FWL		SE NW		12		10.0 S		22.0 E		S	
Top of Uppermost Producing Zone		2567 FSL 2142 FWL		NE SW		12		10.0 S		22.0 E		S	
At Total Depth		2567 FSL 2142 FWL		NE SW		12		10.0 S		22.0 E		S	
21. COUNTY UINTAH				22. DISTANCE TO NEAREST LEASE LINE (Feet) 2567				23. NUMBER OF ACRES IN DRILLING UNIT 1674					
				25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 865				26. PROPOSED DEPTH MD: 8478 TVD: 8454					
27. ELEVATION - GROUND LEVEL 5200				28. BOND NUMBER 22013542				29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 43-8496					
Hole, Casing, and Cement Information													
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement		Sacks	Yield	Weight		
Surf	11	8.625	0 - 2170	28.0	J-55 LT&C	0.2	Type V		180	1.15	15.8		
							Class G		270	1.15	15.8		
Prod	7.875	4.5	0 - 8478	11.6	I-80 LT&C	12.5	Premium Lite High Strength		270	3.38	11.0		
							50/50 Poz		1150	1.31	14.3		
ATTACHMENTS													
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES													
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER						<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN							
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)						<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER							
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)						<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP							
NAME Gina Becker				TITLE Regulatory Analyst II				PHONE 720 929-6086					
SIGNATURE				DATE 09/13/2011				EMAIL gina.becker@anadarko.com					
API NUMBER ASSIGNED 43047519650000				APPROVAL  Permit Manager									

RECEIVED: December 12, 2011

Kerr-McGee Oil & Gas Onshore. L.P.**NBU 1022-12K1BS**

Surface: 2473 FNL / 2359 FWL SENW
BHL: 2567 FSL / 2142 FWL NESW

Section 12 T10S R22E

Uintah County, Utah
Mineral Lease: UT ST UO 01197-A ST

ONSHORE ORDER NO. 1**DRILLING PROGRAM**

1. & 2. **Estimated Tops of Important Geologic Markers:**
Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1066	
Birds Nest	1358	Water
Mahogany	1722	Water
Wasatch	4102	Gas
Mesaverde	6275	Gas
MVU2	7236	Gas
MVL1	7788	Gas
TVD	8454	
TD	8478	

3. **Pressure Control Equipment** (Schematic Attached)

Please refer to the attached Drilling Program

4. **Proposed Casing & Cementing Program:**

Please refer to the attached Drilling Program

5. **Drilling Fluids Program:**

Please refer to the attached Drilling Program

6. **Evaluation Program:**

Please refer to the attached Drilling Program

7. **Abnormal Conditions:**

Maximum anticipated bottom hole pressure calculated at 8454' TVD, approximately equals
5,411 psi 0.64 psi/ft = actual bottomhole gradient

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,539 psi (bottom hole pressure
minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-
(0.22 psi/ft-partial evac gradient x TVD of next csg point))

8. **Anticipated Starting Dates:**

Drilling is planned to commence immediately upon approval of this application.

9. **Variances:**

Please refer to the attached Drilling Program.

Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- *Blowout Prevention Equipment (BOPE) requirements;*
- *Mud program requirements; and*
- *Special drilling operation (surface equipment placement) requirements associated with air drilling.*

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 11 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and

on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.


10. **Other Information:**

Please refer to the attached Drilling Program.



KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP					DATE	September 7, 2011		
WELL NAME	NBU 1022-12K1BS					TD	8,454'	TVD	8,478' MD
FIELD	Natural Buttes		COUNTY	Uintah	STATE	Utah	FINISHED ELEVATION		5199.8
SURFACE LOCATION	SENW	2473 FNL	2359 FWL	Sec 12	T 10S	R 22E			
	Latitude: 39.963944		Longitude: -109.388654		NAD 27				
BTM HOLE LOCATION	NESW	2567 FSL	2142 FWL	Sec 12	T 10S	R 22E			
	Latitude: 39.963279		Longitude: -109.389434		NAD 27				
OBJECTIVE ZONE(S)	Wasatch/Mesaverde								
ADDITIONAL INFO	Regulatory Agencies: UDOGM (Minerals), UDOGM (Surface), UDOGM Tri-County Health Dept.								





KERR-McGEE OIL & GAS ONSHORE LP

DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	LTC	BTC
CONDUCTOR	14"	0-40'						
						3,390	1,880	348,000
SURFACE	8-5/8"	0 to 2,170	28.00	IJ-55	LTC	2.49	1.85	6.54
						7,780	6,350	279,000
PRODUCTION	4-1/2"	0 to 8,478	11.60	I-80	LTC/BTC	1.11	1.16	3.51
								4.61

Surface Casing:

(Burst Assumptions: TD = 12.5 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
Option 1			+ 0.25 pps flocele				
	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
			+ 2% CaCl + 0.25 pps flocele				
SURFACE		NOTE: If well will circulate water to surface, option 2 will be utilized					
Option 2	LEAD	1,670'	65/35 Poz + 6% Gel + 10 pps gilsonite	160	35%	11.00	3.82
			+ 0.25 pps Flocele + 3% salt BWOW				
	TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
			+ 0.25 pps flocele				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION	LEAD	3,598'	Premium Lite II +0.25 pps	270	20%	11.00	3.38
			celloflake + 5 pps gilsonite + 10% gel				
			+ 0.5% extender				
	TAIL	4,880'	50/50 Poz/G + 10% salt + 2% gel	1,150	35%	14.30	1.31
			+ 0.1% R-3				

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Nick Spence / Danny Showers

DATE:**DRILLING SUPERINTENDENT:**

Kenny Gathings / Lovel Young

DATE:

EXHIBIT A
NBU 1022-12K1BS



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK

T10S, R22E, S.L.B.&M.

Found 1991 Aluminum
Cap with Pile of Stones.
Fence Post on SE side
of Cap.


S89°59'W - 40.01 (G.L.O.)
2640.76' (Measured)

N89°39'W - 40.01 (G.L.O.)
N89°41'22"W - 2640.46' (Meas.)

Found 1991 Aluminum
Cap in Pile of Stones.
Fence Post on North
side of Cap.

S89°57'13"W (Basis of Bearings)

N0°01'W (G.L.O.)
N00°25'25"E - 5276.36' (Meas.)



**WELL LOCATION:
NBU 1022-12K1BS**

ELEV. UNGRADED GROUND = 5199.8'

NBU 1022-12K1BS (Surface Position)
NAD 83 LATITUDE = 39.963909° (39° 57' 50.074")
LONGITUDE = 109.389334° (109° 23' 21.604")
NAD 27 LATITUDE = 39.963944° (39° 57' 50.197")
LONGITUDE = 109.388654° (109° 23' 19.154")

NBU 1022-12K1BS (Bottom Hole)
NAD 83 LATITUDE = 39.963245° (39° 57' 47.681")
LONGITUDE = 109.390114° (109° 23' 24.412")
NAD 27 LATITUDE = 39.963279° (39° 57' 47.804")
LONGITUDE = 109.389434° (109° 23' 21.962")

Found Uintah
County Aluminum
Cap on 3/4" rebar.
Pile of Stones

Found 1991 Aluminum
Cap in Pile of Stones.
Fence Post on East
side of Cap.

N89°52'55"W - 5312.93' (Meas.)
S89°59'W - 80.02 (G.L.O.)

NOTES:

▲ = Section Corners Located

- Well footages are measured at right angles to the Section Lines.
- G.L.O. distances are shown in feet or chains.
1 chain = 66 feet.
- The Bottom of hole bears S42°01'55"W 326.38' from the Surface Position.
- Bearings are based on Global Positioning Satellite observations.
- Basis of elevation is Tri-Sta "Two Water" located in the NW $\frac{1}{4}$ of Section 1, T10S, R21E, S.L.B.&M. The elevation of this Tri-Sta is shown on the Big Pack Mtn NE 7.5 Min. Quadrangle as being 5238'.

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD: NBU 1022-12F4

**NBU 1022-12K1BS
WELL PLAT**

2567' FSL, 2142' FWL (Bottom Hole)
NE $\frac{1}{4}$ SW $\frac{1}{4}$ OF SECTION 12, T10S, R22E,
S.L.B.&M., UTAH COUNTY, UTAH.

CONSULTING, LLC
2155 North Main Street
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182



SURVEYOR'S CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

PROFESSIONAL LAND SURVEYOR
REGISTRATION NO. 6028691
STATE OF UTAH
2-15-11

TIMBERLINE

(435) 789-1365

ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078


DATE SURVEYED: 01-31-11	SURVEYED BY: R.Y.	SHEET NO:
DATE DRAWN: 02-11-11	DRAWN BY: E.M.S.	4
SCALE: 1" = 1000'	Date Last Revised:	4 OF 18

RECEIVED: September 13, 2011

WELL NAME	SURFACE POSITION					BOTTOM HOLE				
	NAD83		NAD27		FOOTAGES	NAD83		NAD27		FOOTAGES
	LATITUDE	LONGITUDE	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	LATITUDE	LONGITUDE	
NBU 1022-12K4CS	39°57'49.906"	109°23'21.286"	39°57'50.029"	109°23'18.836"	2490' FNL	39°57'37.860"	109°23'24.465"	39°57'37.983"	109°23'22.016"	1573' FSL
NBU 1022-12K4BS	39°57'49.962"	109°23'21.392"	39°57'50.085"	109°23'18.942"	2384' FWL	39°57'41.130"	109°23'24.443"	39°57'41.253"	109°23'21.994"	2146' FWL
NBU 1022-12K1CS	39°57'50.018"	109°23'21.498"	39°57'50.141"	109°23'19.048"	2479' FNL	39°57'44.410"	109°23'24.421"	39°57'44.533"	109°23'21.972"	2236' FSL
NBU 1022-12K1BS	39°57'50.074"	109°23'21.604"	39°57'50.197"	109°23'19.154"	2473' FNL	39°57'47.681"	109°23'24.412"	39°57'47.804"	109°23'21.962"	2567' FSL
NBU 1022-12E4CS	39°57'50.130"	109°23'21.709"	39°57'50.253"	109°23'19.260"	2467' FNL	39°57'49.166"	109°23'41.345"	39°57'49.289"	109°23'38.894"	2565' FNL
NBU 1022-12F4CS	39°57'50.186"	109°23'21.815"	39°57'50.309"	109°23'19.366"	2462' FNL	39°57'50.787"	109°23'24.392"	39°57'50.910"	109°23'21.942"	2401' FNL
NBU 1022-12F4BS	39°57'50.186"	109°23'21.815"	39°57'50.309"	109°23'19.366"	2342' FWL	39°57'50.787"	109°23'24.392"	39°57'50.910"	109°23'21.942"	2141' FWL

RELATIVE COORDINATES - From Surface Position to Bottom Hole

WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAST
NBU 1022-12K4CS	-1,219.5'	-246.6'	NBU 1022-12K4BS	-894.1'	-236.9'	NBU 1022-12K1CS	-567.8'	-227.2'	NBU 1022-12K1BS	-242.4'	-218.5'
WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAST						
NBU 1022-12E4CS	-98.8'	-1,529.2'	NBU 1022-12F4CS	60.7'	-200.7'						



Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 1022-12F4

WELL PAD INTERFERENCE PLAT
WELLS - NBU 1022-12K4CS, NBU 1022-12K4BS,
NBU 1022-12K1CS, NBU 1022-12K1BS,
NBU 1022-12E4CS & NBU 1022-12F4CS
LOCATED IN SECTION 12, T10S, R22E,
S.L.B.&M., UTAH COUNTY, UTAH.



CONSULTING, LLC
2155 North Main Street
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182

TIMBERLINE


(435) 789-1365

ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

DATE SURVEYED: 01-31-11	SURVEYED BY: R.Y.	SHEET NO:
DATE DRAWN: 02-11-11	DRAWN BY: E.M.S.	7 7 OF 18
SCALE: 1" = 60'	Date Last Revised:	

RECEIVED: September 13, 2011

PLEASE NOTE: LOCATIONS OF PROPOSED PIPELINES DISPLAYED WITHIN THE PAD AREA ARE FOR VISUALIZATION PURPOSES ONLY. ACTUAL LOCATIONS TO BE DETERMINED DURING CONSTRUCTION.



WELL PAD - NBU 1022-12F4 DESIGN SUMMARY

EXISTING GRADE @ CENTER OF WELL PAD = 5199.7'
FINISHED GRADE ELEVATION = 5197.5'
CUT SLOPES = 1.5:1
FILL SLOPES = 1.5:1
TOTAL WELL PAD AREA = 3.65 ACRES
TOTAL DAMAGE AREA = 6.49 ACRES
SHRINKAGE FACTOR = 1.10
SWELL FACTOR = 1.00

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 1022-12F4

WELL PAD - LOCATION LAYOUT
NBU 1022-12K4CS, NBU 1022-12K4BS,
NBU 1022-12K1CS, NBU 1022-12K1BS,
NBU 1022-12E4CS & NBU 1022-12F4CS
LOCATED IN SECTION 12, T10S, R22E,
S.L.B.&M., UINTAH COUNTY, UTAH

WELL PAD QUANTITIES

TOTAL CUT FOR WELL PAD = 16,630 C.Y.
TOTAL FILL FOR WELL PAD = 10,730 C.Y.
TOPSOIL @ 6" DEPTH = 2,943 C.Y.
EXCESS MATERIAL = 5,900 C.Y.

RESERVE PIT QUANTITIES

TOTAL CUT FOR RESERVE PIT
+/- 11,020 C.Y.
RESERVE PIT CAPACITY (2' OF FREEBOARD)
+/- 42,290 BARRELS



CONSULTING, LLC
2155 North Main Street
Sheridan, WY 82801
Phone 307-674-0609
Fax 307-674-0182

TIMBERLINE
ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365


WELL PAD LEGEND

- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- PROPOSED BOTTOM HOLE LOCATION
- EXISTING CONTOURS (2' INTERVAL)
- PROPOSED CONTOURS (2' INTERVAL)
- PPL - PROPOSED PIPELINE
- EPL - EXISTING PIPELINE




HORIZONTAL 0 30' 60' 1" = 60'
2' CONTOURS

SCALE: 1"=60' DATE: 3/8/11 SHEET NO: 8
REVISED: TAR 4/15/11 8 OF 18



CROSS SECTION A-A'



CROSS SECTION B-B'

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 1022-12F4

WELL PAD - CROSS SECTIONS
NBU 1022-12K4CS, NBU 1022-12K4BS,
NBU 1022-12K1CS, NBU 1022-12K1BS,
NBU 1022-12E4CS & NBU 1022-12F4CS
LOCATED IN SECTION 12, T10S, R22E,
S.L.B.&M., UTAH COUNTY, UTAH



CONSULTING, LLC
2155 North Main Street
Sheridan, WY 82801
Phone 307-674-0609
Fax 307-674-0182

TIMBERLINE
ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365

HORIZONTAL 0 50' 100' 1" = 100'
VERTICAL 0 10' 20' 1" = 20'

Scale: 1"=100'


Date: 3/8/11

SHEET NO:

9

9 OF 18

RECEIVED: September 13, 2011



PLEASE NOTE: LOCATIONS OF FACILITIES AND PROPOSED PIPELINES DISPLAYED WITHIN THE PAD AREA ARE FOR VISUALIZATION PURPOSES ONLY. ACTUAL LOCATIONS TO BE DETERMINED DURING CONSTRUCTION.

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 1022-12F4

WELL PAD - FACILITIES DIAGRAM

NBU 1022-12K4CS, NBU 1022-12K4BS,
NBU 1022-12K1CS, NBU 1022-12K1BS,
NBU 1022-12E4CS & NBU 1022-12F4CS
LOCATED IN SECTION 12, T10S, R22E,
S.L.B.&M., UTAH COUNTY, UTAH



CONSULTING, LLC
2155 North Main Street
Sheridan, WY 82801
Phone 307-674-0609
Fax 307-674-0182

WELL PAD LEGEND

- EXISTING WELL LOCATION
- PROPOSED WELL LOCATION
- PPL — PROPOSED PIPELINE
- EPL — EXISTING PIPELINE



HORIZONTAL 0 30' 60' 1" = 60'

TIMBERLINE
ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365

Scale: 1"=60'
REVISED:

Date: 3/8/11
TAR
4/15/11

SHEET NO:

10 10 OF 18

RECEIVED: September 13, 2011




PHOTO VIEW: FROM PIT CORNER D TO LOCATION STAKE

CAMERA ANGLE: NORTHEASTRLY




PHOTO VIEW: FROM BEGINNING OF PROPOSED ROAD

CAMERA ANGLE: SOUTHWESTERLY

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 1022-12F4

LOCATION PHOTOS

NBU 1022-12K4CS, NBU 1022-12K4BS,
NBU 1022-12K1CS, NBU 1022-12K1BS,
NBU 1022-12E4CS & NBU 1022-12F4CS
LOCATED IN SECTION 12, T10S, R22E,
S.L.B.&M., Uintah County, Utah.



CONSULTING, LLC
2155 North Main Street
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182


TIMBERLINE

(435) 789-1365

ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

DATE PHOTOS TAKEN: 02-11-11	PHOTOS TAKEN BY: M.S.B.	SHEET NO: 11 11 OF 18
DATE DRAWN: 02-11-11	DRAWN BY: E.M.S.	
Date Last Revised:		

RECEIVED: September 13, 2011



Legend

- Proposed Well Location
- Natural Buttes Unit Boundary
- Access Route - Proposed

Distance From Well Pad - NBU 1022-12F4 To Unit Boundary: ±2,912ft

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202

WELL PAD - NBU 1022-12F4

TOPO A

NBU 1022-12K4CS, NBU 1022-12K4BS,
NBU 1022-12K1CS, NBU 1022-12K1BS,
NBU 1022-12E4CS & NBU 1022-12F4CS
LOCATED IN SECTION 12, T10S, R22E,
S.L.B.&M., UTAH COUNTY, UTAH



CONSULTING, LLC
2155 North Main Street
Sheridan, WY 82801
Phone (307) 674-0609
Fax (307) 674-0182



Scale: 1:100,000

NAD83 USP Central

Sheet No:


Drawn: TL
Revised:

Date: 8 Mar 2011
Date:

12

12 of 18

RECEIVED: September 13, 2011



NBU 1022-12K4CS
NBU 1022-12K4BS
NBU 1022-12K1CS
NBU 1022-12K1BS
NBU 1022-12E4CS
NBU 1022-12F4CS

Legend

- Well - Proposed
- Well - Existing
- Well Pad
- Road - Proposed
- Road - Existing
- County Road
- Bureau of Land Management
- Indian Reservation
- State
- Private

Total Proposed Road Length: ±610ft

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202

WELL PAD - NBU 1022-12F4

TOPO B


NBU 1022-12K4CS, NBU 1022-12K4BS,
NBU 1022-12K1CS, NBU 1022-12K1BS,
NBU 1022-12E4CS & NBU 1022-12F4CS
LOCATED IN SECTION 12, T10S, R22E,
S.L.B.&M., UTAH COUNTY, UTAH



Scale: 1" = 2,000ft
NAD83 USP Central
Drawn: TL
Revised: Date: 8 Mar 2011

Sheet No:
13
13 of 18

RECEIVED: September 13, 2011

**Legend**

- Well - Proposed
- Bottom Hole - Proposed
- Well Path
- Bottom Hole - Existing
- Well Pad
- Well - 1 Mile Radius

Well locations derived from State of Utah, Dept. of Natural Resources, Division of Oil, Gas and Mining

Kerr-McGee Oil & Gas Onshore, LP
 1099 18th Street, Denver, Colorado 80202

WELL PAD - NBU 1022-12F4**TOPO C**

NBU 1022-12K4CS, NBU 1022-12K4BS,
 NBU 1022-12K1CS, NBU 1022-12K1BS,
 NBU 1022-12E4CS & NBU 1022-12F4CS
 LOCATED IN SECTION 12, T10S, R22E,
 S.L.B.&M., UTAH COUNTY, UTAH



CONSULTING, LLC
 2155 North Main Street
 Sheridan, WY 82801
 Phone (307) 674-0609
 Fax (307) 674-0182



- Producing
- ⊙ Active
- ⊙ Spudded (Drilling commenced: Not yet completed)
- ▲ Approved permit (APD); not yet spudded
- New Permit (Not yet approved or drilled)
- ⊕ Inactive
- ⊗ Drilling Operations Suspended
- Temporarily-Abandoned
- Shut-In
- Plugged and Abandoned
- ⊗ Location Abandoned
- ⊗ Dry hole marker, buried
- ⊗ Returned APD (Unapproved)

Scale: 1" = 2,000ft

NAD83 USP Central


Sheet No:

 Drawn: TL
 Revised:

 Date: 8 Mar 2011
 Date:
14

14 of 18

RECEIVED: September 13, 2011



Proposed Liquid Pipeline	Length
Proposed 6" (Max.) (Meter House to Edge of Pad)	±470ft
Proposed 6" (Max.) (Edge of Pad to 12F Intersection)	±515ft
TOTAL PROPOSED LIQUID PIPELINE =	±985ft

Proposed Gas Pipeline	Length
Proposed 6" (Meter House to Edge of Pad)	±470ft
Proposed 6" (Edge of Pad to 12F Intersection)	±515ft
TOTAL PROPOSED GAS PIPELINE =	±985ft

Legend

- Well - Proposed
- Well - Existing
- Well Pad
- - - Gas Pipeline - Proposed
- . - Gas Pipeline - To Be Upgraded
- - - Gas Pipeline - Existing
- - - Liquid Pipeline - Proposed
- - - Liquid Pipeline - Existing
- - - Road - Proposed
- - - Road - Existing
- Bureau of Land Management
- Indian Reservation
- State
- Private

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202


WELL PAD - NBU 1022-12F4

TOPO D
NBU 1022-12K4CS, NBU 1022-12K4BS,
NBU 1022-12K1CS, NBU 1022-12K1BS,
NBU 1022-12E4CS & NBU 1022-12F4CS
LOCATED IN SECTION 12, T10S, R22E,
S.L.B.&M., UTAH COUNTY, UTAH



Scale: 1" = 2,000ft	NAD83 USP Central	Sheet No:
Drawn: JFE	Date: 8 Mar 2011	15
Revised: TL	Date: 19 Apr 2011	15 of 18

RECEIVED: September 13, 2011



Proposed Liquid Pipeline	Length
Proposed 6" (Max.) (Meter House to Edge of Pad)	±470ft
Proposed 6" (Max.) (Edge of Pad to 12F Intersection)	±515ft
TOTAL PROPOSED LIQUID PIPELINE =	±985ft

Proposed Gas Pipeline	Length
Proposed 6" (Meter House to Edge of Pad)	±470ft
Proposed 6" (Edge of Pad to 12F Intersection)	±515ft
TOTAL PROPOSED GAS PIPELINE =	±985ft

Legend

- Well - Proposed
- Well - Existing
- Well Pad
- Gas Pipeline - Proposed
- Gas Pipeline - To Be Upgraded
- Gas Pipeline - Existing
- Liquid Pipeline - Proposed
- Liquid Pipeline - Existing
- Road - Proposed
- Road - Existing
- Bureau of Land Management
- Indian Reservation
- State
- Private

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202


WELL PAD - NBU 1022-12F4

TOPO D2 (PAD & PIPELINE DETAIL)
NBU 1022-12K4CS, NBU 1022-12K4BS,
NBU 1022-12K1CS, NBU 1022-12K1BS,
NBU 1022-12E4CS & NBU 1022-12F4CS
LOCATED IN SECTION 12, T10S, R22E,
S.L.B.&M., UTAH COUNTY, UTAH



Scale: 1" = 500ft	NAD83 USP Central	Sheet No:
Drawn: JFE	Date: 8 Mar 2011	16
Revised: TL	Date: 19 Apr 2011	16 of 18

RECEIVED: September 13, 2011



Legend

- Well - Proposed
- Bottom Hole - Proposed
- Bottom Hole - Existing
- Well Path
- Well Pad
- ▬ Lease Boundary
- Gas Pipeline - Proposed
- Gas Pipeline - To Be Upgraded
- Gas Pipeline - Existing
- Liquid Pipeline - Proposed
- Liquid Pipeline - Existing
- Road - Proposed
- Road - Existing
- Bureau of Land Management
- Indian Reservation
- State
- Private

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202

WELL PAD - NBU 1022-12F4

TOPO E
NBU 1022-12K4CS, NBU 1022-12K4BS,
NBU 1022-12K1CS, NBU 1022-12K1BS,
NBU 1022-12E4CS & NBU 1022-12F4CS
LOCATED IN SECTION 12, T10S, R22E,
S.L.B.&M., UTAH COUNTY, UTAH

609
CONSULTING, LLC
2155 North Main Street
Sheridan, WY 82801
Phone (307) 674-0609
Fax (307) 674-0182



Scale: 1" = 2,000ft

NAD83 USP Central

Sheet No:

Drawn: TL
Revised: TL

Date: 8 Mar 2011
Date: 19 Apr 2011

17


17 of 18

RECEIVED: September 13, 2011



Kerr-McGee Oil & Gas Onshore, LP
WELL PAD – NBU 1022-12F4
WELLS – NBU 1022-12K4CS, NBU 1022-12K4BS, NBU 1022-12K1CS,
NBU 1022-12K1BS, NBU 1022-12E4CS & NBU 1022-12F4CS
Section 12, T10S, R22E, S.L.B.&M.

From the intersection of U.S. Highway 40 and 500 East Street in Vernal, Utah, proceed in an easterly then southerly direction along U.S. Highway 40 approximately 3.3 miles to the junction of State Highway 45. Exit right and proceed in a southerly direction along State Highway 45 approximately 20.2 miles to the junction of the Glen Bench Road (County B Road 3260). Exit right and proceed in a southwesterly direction along the Glen Bench Road approximately 14.4 miles to the intersection of the Fidlar Road (County B Road 3410) which road intersection is approximately 400 feet northeast of the Mountain Fuel Bridge at the White River. Exit left and proceed in a southeasterly direction along the Fidlar Road approximately 4.4 miles to the intersection of the Seven Sisters Road (County B Road 3420). Exit right and proceed in a southeasterly then southerly direction along the Seven Sisters Road approximately 4.6 miles to a service road to the southwest. Exit right and proceed in a southwesterly direction along the service road approximately 0.3 miles to the proposed access road. Follow the road flags in a southwesterly direction approximately 610 feet to the proposed well location.

Total distance from Vernal, Utah to the proposed well location is approximately 47.3 miles in a southerly direction.



WELL DETAILS: NBU 1022-12K1BS						
GL 5198 & KB 4 @ 5202.00ft (ASSUMED)						
+N/-S 0.00	+E/-W 0.00	Northing 14516993.85	Easting 2091935.29	Latitude 39° 57' 50.198 N	Longitude 109° 23' 19.154 W	
DESIGN TARGET DETAILS						
Name PBHL	TVD 8454.00	+N/-S -242.20	+E/-W -218.61	Northing 14516747.74	Easting 2091721.09	Latitude 39° 57' 47.804 N
- plan hits target center						
				Longitude 109° 23' 21.962 W	Shape Circle (Radius: 25.00)	



SECTION DETAILS									
	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect
	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00
	750.00	9.00	222.07	748.15	-26.18	-23.63	2.00	222.07	35.27
	2352.55	9.00	222.07	2330.97	-212.28	-191.61	0.00	0.00	285.96
	2866.84	0.00	0.00	2843.15	-242.20	-218.61	1.75	180.00	326.27
	8477.69	0.00	0.00	8454.00	-242.20	-218.61	0.00	0.00	326.27
	PBHL_NBU 1022-12K1BS								
PROJECT DETAILS: UTAH - UTM (feet), NAD27, Zone 12N							FORMATION TOP DETAILS		
Geodetic System: Universal Transverse Mercator (US Survey Feet) Datum: NAD 1927 (NADCON CONUS) Ellipsoid: Clarke 1866 Zone: Zone 12N (114 W to 108 W) Location: SECTION 12 T10S R22E System Datum: Mean Sea Level							TVDPath	MDPath	Formation
							1066.00	1071.81	GREEN RIVER
							4102.00	4125.69	WASATCH
							6275.00	6298.69	MESAVERDE

CASING DETAILS			
TVD	MD	Name	Size
2172.00	2191.60	8 5/8"	8.625

RECEIVED



US ROCKIES REGION PLANNING

UTAH - UTM (feet), NAD27, Zone 12N

NBU 1022-12F4 PAD

NBU 1022-12K1BS

OH

Plan: PLAN #1 PRELIMINARY

Standard Planning Report

26 August, 2011





SDI Planning Report



Database:	EDM5000-RobertS-Local	Local Co-ordinate Reference:	Well NBU 1022-12K1BS
Company:	US ROCKIES REGION PLANNING	TVD Reference:	GL 5198 & KB 4 @ 5202.00ft (ASSUMED)
Project:	UTAH - UTM (feet), NAD27, Zone 12N	MD Reference:	GL 5198 & KB 4 @ 5202.00ft (ASSUMED)
Site:	NBU 1022-12F4 PAD	North Reference:	True
Well:	NBU 1022-12K1BS	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1 PRELIMINARY		

Project	UTAH - UTM (feet), NAD27, Zone 12N		
Map System:	Universal Transverse Mercator (US Survey Feet)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Zone 12N (114 W to 108 W)		

Site	NBU 1022-12F4 PAD, SECTION 12 T10S R22E		
Site Position:		Northing:	14,516,999.17 usft
From:	Lat/Long	Easting:	2,091,927.06 usft
Position Uncertainty:	0.00 ft	Slot Radius:	13.200 in
		Latitude:	39° 57' 50.252 N
		Longitude:	109° 23' 19.259 W
		Grid Convergence:	1.04 °

Well	NBU 1022-12K1BS, 2473 FNL 2359 FWL		
Well Position	+N/-S	-5.46 ft	Northing:
	+E/-W	8.13 ft	Easting:
Position Uncertainty	0.00 ft		Wellhead Elevation:
			Latitude:
			Longitude:
			Ground Level:

Wellbore	OH				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	08/26/11	11.00	65.85	52,303

Design	PLAN #1 PRELIMINARY			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.00	0.00	0.00	222.07

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
750.00	9.00	222.07	748.15	-26.18	-23.63	2.00	2.00	0.00	222.07	
2,352.55	9.00	222.07	2,330.97	-212.28	-191.61	0.00	0.00	0.00	0.00	
2,866.84	0.00	0.00	2,843.15	-242.20	-218.61	1.75	-1.75	0.00	180.00	
8,477.69	0.00	0.00	8,454.00	-242.20	-218.61	0.00	0.00	0.00	0.00	PBHL_NBU 1022-12K1BS



Database:	EDM5000-RobertS-Local	Local Co-ordinate Reference:	Well NBU 1022-12K1BS
Company:	US ROCKIES REGION PLANNING	TVD Reference:	GL 5198 & KB 4 @ 5202.00ft (ASSUMED)
Project:	UTAH - UTM (feet), NAD27, Zone 12N	MD Reference:	GL 5198 & KB 4 @ 5202.00ft (ASSUMED)
Site:	NBU 1022-12F4 PAD	North Reference:	True
Well:	NBU 1022-12K1BS	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1 PRELIMINARY		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
Start Build 2.00									
400.00	2.00	222.07	399.98	-1.30	-1.17	1.75	2.00	2.00	0.00
500.00	4.00	222.07	499.84	-5.18	-4.68	6.98	2.00	2.00	0.00
600.00	6.00	222.07	599.45	-11.65	-10.52	15.69	2.00	2.00	0.00
700.00	8.00	222.07	698.70	-20.70	-18.68	27.88	2.00	2.00	0.00
750.00	9.00	222.07	748.15	-26.18	-23.63	35.27	2.00	2.00	0.00
Start 1602.55 hold at 750.00 MD									
800.00	9.00	222.07	797.54	-31.99	-28.87	43.09	0.00	0.00	0.00
900.00	9.00	222.07	896.31	-43.60	-39.35	58.74	0.00	0.00	0.00
1,000.00	9.00	222.07	995.07	-55.21	-49.84	74.38	0.00	0.00	0.00
1,071.81	9.00	222.07	1,066.00	-63.55	-57.36	85.61	0.00	0.00	0.00
GREEN RIVER									
1,100.00	9.00	222.07	1,093.84	-66.83	-60.32	90.02	0.00	0.00	0.00
1,200.00	9.00	222.07	1,192.61	-78.44	-70.80	105.67	0.00	0.00	0.00
1,300.00	9.00	222.07	1,291.38	-90.05	-81.28	121.31	0.00	0.00	0.00
1,400.00	9.00	222.07	1,390.15	-101.66	-91.76	136.95	0.00	0.00	0.00
1,500.00	9.00	222.07	1,488.92	-113.28	-102.24	152.60	0.00	0.00	0.00
1,600.00	9.00	222.07	1,587.69	-124.89	-112.73	168.24	0.00	0.00	0.00
1,700.00	9.00	222.07	1,686.46	-136.50	-123.21	183.88	0.00	0.00	0.00
1,800.00	9.00	222.07	1,785.22	-148.11	-133.69	199.53	0.00	0.00	0.00
1,900.00	9.00	222.07	1,883.99	-159.73	-144.17	215.17	0.00	0.00	0.00
2,000.00	9.00	222.07	1,982.76	-171.34	-154.65	230.81	0.00	0.00	0.00
2,100.00	9.00	222.07	2,081.53	-182.95	-165.13	246.46	0.00	0.00	0.00
2,191.60	9.00	222.07	2,172.00	-193.59	-174.74	260.79	0.00	0.00	0.00
8 5/8"									
2,200.00	9.00	222.07	2,180.30	-194.57	-175.62	262.10	0.00	0.00	0.00
2,300.00	9.00	222.07	2,279.07	-206.18	-186.10	277.74	0.00	0.00	0.00
2,352.55	9.00	222.07	2,330.97	-212.28	-191.61	285.96	0.00	0.00	0.00
Start Drop -1.75									
2,400.00	8.17	222.07	2,377.89	-217.54	-196.35	293.05	1.75	-1.75	0.00
2,500.00	6.42	222.07	2,477.08	-226.96	-204.86	305.74	1.75	-1.75	0.00
2,600.00	4.67	222.07	2,576.60	-234.14	-211.33	315.41	1.75	-1.75	0.00
2,700.00	2.92	222.07	2,676.38	-239.05	-215.77	322.02	1.75	-1.75	0.00
2,800.00	1.17	222.07	2,776.31	-241.70	-218.16	325.59	1.75	-1.75	0.00
2,866.84	0.00	0.00	2,843.15	-242.20	-218.61	326.27	1.75	-1.75	206.36
Start 5610.85 hold at 2866.84 MD									
2,900.00	0.00	0.00	2,876.31	-242.20	-218.61	326.27	0.00	0.00	0.00
3,000.00	0.00	0.00	2,976.31	-242.20	-218.61	326.27	0.00	0.00	0.00
3,100.00	0.00	0.00	3,076.31	-242.20	-218.61	326.27	0.00	0.00	0.00
3,200.00	0.00	0.00	3,176.31	-242.20	-218.61	326.27	0.00	0.00	0.00
3,300.00	0.00	0.00	3,276.31	-242.20	-218.61	326.27	0.00	0.00	0.00
3,400.00	0.00	0.00	3,376.31	-242.20	-218.61	326.27	0.00	0.00	0.00
3,500.00	0.00	0.00	3,476.31	-242.20	-218.61	326.27	0.00	0.00	0.00
3,600.00	0.00	0.00	3,576.31	-242.20	-218.61	326.27	0.00	0.00	0.00
3,700.00	0.00	0.00	3,676.31	-242.20	-218.61	326.27	0.00	0.00	0.00
3,800.00	0.00	0.00	3,776.31	-242.20	-218.61	326.27	0.00	0.00	0.00
3,900.00	0.00	0.00	3,876.31	-242.20	-218.61	326.27	0.00	0.00	0.00



SDI
Planning Report



Database:	EDM5000-RobertS-Local	Local Co-ordinate Reference:	Well NBU 1022-12K1BS
Company:	US ROCKIES REGION PLANNING	TVD Reference:	GL 5198 & KB 4 @ 5202.00ft (ASSUMED)
Project:	UTAH - UTM (feet), NAD27, Zone 12N	MD Reference:	GL 5198 & KB 4 @ 5202.00ft (ASSUMED)
Site:	NBU 1022-12F4 PAD	North Reference:	True
Well:	NBU 1022-12K1BS	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1 PRELIMINARY		

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
4,000.00	0.00	0.00	3,976.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
4,100.00	0.00	0.00	4,076.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
4,125.69	0.00	0.00	4,102.00	-242.20	-218.61	326.27	0.00	0.00	0.00	
WASATCH										
4,200.00	0.00	0.00	4,176.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
4,300.00	0.00	0.00	4,276.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
4,400.00	0.00	0.00	4,376.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
4,500.00	0.00	0.00	4,476.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
4,600.00	0.00	0.00	4,576.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
4,700.00	0.00	0.00	4,676.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
4,800.00	0.00	0.00	4,776.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
4,900.00	0.00	0.00	4,876.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
5,000.00	0.00	0.00	4,976.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
5,100.00	0.00	0.00	5,076.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
5,200.00	0.00	0.00	5,176.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
5,300.00	0.00	0.00	5,276.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
5,400.00	0.00	0.00	5,376.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
5,500.00	0.00	0.00	5,476.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
5,600.00	0.00	0.00	5,576.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
5,700.00	0.00	0.00	5,676.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
5,800.00	0.00	0.00	5,776.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
5,900.00	0.00	0.00	5,876.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
6,000.00	0.00	0.00	5,976.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
6,100.00	0.00	0.00	6,076.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
6,200.00	0.00	0.00	6,176.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
6,298.69	0.00	0.00	6,275.00	-242.20	-218.61	326.27	0.00	0.00	0.00	
MESAVERDE										
6,300.00	0.00	0.00	6,276.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
6,400.00	0.00	0.00	6,376.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
6,500.00	0.00	0.00	6,476.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
6,600.00	0.00	0.00	6,576.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
6,700.00	0.00	0.00	6,676.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
6,800.00	0.00	0.00	6,776.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
6,900.00	0.00	0.00	6,876.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
7,000.00	0.00	0.00	6,976.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
7,100.00	0.00	0.00	7,076.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
7,200.00	0.00	0.00	7,176.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
7,300.00	0.00	0.00	7,276.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
7,400.00	0.00	0.00	7,376.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
7,500.00	0.00	0.00	7,476.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
7,600.00	0.00	0.00	7,576.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
7,700.00	0.00	0.00	7,676.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
7,800.00	0.00	0.00	7,776.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
7,900.00	0.00	0.00	7,876.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
8,000.00	0.00	0.00	7,976.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
8,100.00	0.00	0.00	8,076.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
8,200.00	0.00	0.00	8,176.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
8,300.00	0.00	0.00	8,276.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
8,400.00	0.00	0.00	8,376.31	-242.20	-218.61	326.27	0.00	0.00	0.00	
8,477.69	0.00	0.00	8,454.00	-242.20	-218.61	326.27	0.00	0.00	0.00	
TD at 8477.69 - PBHL_NBU 1022-12K1BS										

Database:	EDM5000-RobertS-Local	Local Co-ordinate Reference:	Well NBU 1022-12K1BS
Company:	US ROCKIES REGION PLANNING	TVD Reference:	GL 5198 & KB 4 @ 5202.00ft (ASSUMED)
Project:	UTAH - UTM (feet), NAD27, Zone 12N	MD Reference:	GL 5198 & KB 4 @ 5202.00ft (ASSUMED)
Site:	NBU 1022-12F4 PAD	North Reference:	True
Well:	NBU 1022-12K1BS	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	PLAN #1 PRELIMINARY		

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL_NBU 1022-12K1E - plan hits target center - Circle (radius 25.00)	0.00	0.00	8,454.00	-242.20	-218.61	14,516,747.74	2,091,721.08	39° 57' 47.804 N	109° 23' 21.962 W

Casing Points					
Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (in)	Hole Diameter (in)	
2,191.60	2,172.00	8 5/8"	8.625	11.000	

Formations					
Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
1,071.81	1,066.00	GREEN RIVER			
4,125.69	4,102.00	WASATCH			
6,298.69	6,275.00	MESAVERDE			

Plan Annotations					
Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates			
		+N/-S (ft)	+E/-W (ft)	Comment	
300.00	300.00	0.00	0.00	Start Build 2.00	
750.00	748.15	-26.18	-23.63	Start 1602.55 hold at 750.00 MD	
2,352.55	2,330.97	-212.28	-191.61	Start Drop -1.75	
2,866.84	2,843.15	-242.20	-218.61	Start 5610.85 hold at 2866.84 MD	
8,477.69	8,454.00	-242.20	-218.61	TD at 8477.69	

NBU 1022-12E4CS/ 1022-12F4CS/
 1022-12K1BS/ 1022-12K1CS
 1022-12K4BS/ 1022-12K4CS

Surface Use Plan of Operations
 1 of 9

NBU 1022-12E4CS			
Surface:	2467 FNL / 2350 FWL	SENW	Lot
BHL:	2565 FNL / 822 FWL	SWNW	Lot
NBU 1022-12F4CS			
Surface:	2462 FNL / 2342 FWL	SENW	Lot
BHL:	2401 FNL / 2141 FWL	SENW	Lot
NBU 1022-12K1BS			
Surface:	2473 FNL / 2359 FWL	SENW	Lot
BHL:	2567 FSL / 2142 FWL	NESW	Lot
NBU 1022-12K1CS			
Surface:	2479 FNL / 2367 FWL	SENW	Lot
BHL:	2236 FSL / 2144 FWL	NESW	Lot
NBU 1022-12K4BS			
Surface:	2484 FNL / 2375 FWL	SENW	Lot
BHL:	1904 FSL / 2145 FWL	NESW	Lot
NBU 1022-12K4CS			
Surface:	2490 FNL / 2384 FWL	SENW	Lot
BHL:	1573 FSL / 2146 FWL	NESW	Lot

Pad: NBU 1022-12F4 PAD

Section 12 T10S R22E

Mineral Lease: UT ST UO 01197-A ST

Uintah County, Utah

Operator: Kerr-McGee Oil & Gas Onshore LP

This SUPO contains surface operating procedures for Kerr-McGee Oil & Gas Onshore LP (KMG), a wholly owned subsidiary of Anadarko Petroleum Corporation (APC) pertaining to actions that involve the State of Utah School and Institutional Trust Lands Administration (SITLA) in the development of minerals leased to APC/KMG (including but not limited to, APDs/SULAs/ROEs/ROWs and/or easements.)

See associated Utah Division of Oil, Gas, and Mining (UDOGM) Form 3(s), plats, maps, and other attachments for site-specific information on projects represented herein.

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, these wells will be directionally drilled. Refer to Topo Map A for directions to the location and Topo Maps A and B for location of access roads within a 2-mile radius.

RECEIVED: September 13, 2011

NBU 1022-12E4CS/ 1022-12F4CS/
1022-12K1BS/ 1022-12K1CS
1022-12K4BS/ 1022-12K4CS

Surface Use Plan of Operations
2 of 9

A. Existing Roads:

Existing roads consist of county and improved/unimproved lease roads. KMG will maintain existing roads in a condition that is the same as or better than before operations began and in a safe and usable condition. Maintenance of existing roads will continue until final abandonment and reclamation of well pads and/or other facilities. The road maintenance may include, but is not limited to, blading, ditching, culvert installation/cleanout, surfacing, and dust control.

Typically, roads, gathering lines and electrical distribution lines will occupy common disturbance corridors and roadways will be used as working space. All disturbances located in the same corridor will overlap each other to the maximum extent possible; in no case will the maximum disturbance width of the access road and utility corridors exceed 50', unless otherwise approved.

B. Planned Access Roads:

One new access road is proposed (see Topo Map B). The $\pm 610'$ access road will follow the proposed gas and liquid pipelines from the NE side of the pad to the existing access road. Applicable Uintah County encroachment and/or pipeline crossing permits will be obtained prior to construction/development. No other pipelines will be crossed at this location.

If there are roads that are new or to be reconstructed, they will be located, designed, and maintained to meet the standards of SITLA and other commonly accepted Best Management Practices (BMPs). If a new road/corridor were to cross a water of the United States, KMG will adhere to the requirements of applicable Nationwide or Individual Permits of the Department of Army Corps of Engineers.

During the onsite, turnouts, major cut and fills, culverts, bridges, gates, cattle guards, low water crossings, or modifications needed to existing infrastructure/facilities were determined, as applicable, are typically shown on attached Exhibits and Topo maps.

C. Location of Existing and Proposed Facilities:

The NBU 1022-12F4 pad is a newly proposed well pad with no existing wells.

Production facilities (see Well Pad Design Summary and Facilities Diagram):

Production facilities will be installed on the disturbed portion of the well pad and may include bermed components (typically excluding dehy's and/or separators) that contain fluids (i.e. production tanks, produced liquids tanks). The berms will be constructed of compacted subsoil or corrugated metal, impervious, designed to hold 110% of the capacity of the largest tank, and be independent of the back cut. All permanent (on-site six months or longer) above ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earth-tone color chosen at the onsite in coordination with SITLA.

Gathering Facilities:

The following pipeline transmission facilities will apply if the well is productive (see Topo D):

NBU 1022-12E4CS/ 1022-12F4CS/
1022-12K1BS/ 1022-12K1CS
1022-12K4BS/ 1022-12K4CS

Surface Use Plan of Operations
3 of 9

The total gas gathering (steel line pipe with fusion bond epoxy coating) pipeline distances from the meter to the tie in point is $\pm 985'$ and the individual segments are broken up as follows:

- $\pm 470'$ (0.1 miles) –New 6" buried gas pipeline from the meter to the edge of the pad. Please refer to Topo D2 - Pad and Pipeline Detail.
- $\pm 515'$ (0.1 miles) –New 6" buried gas pipeline from the edge of pad to the tie-in at the proposed 1022-12F Intersection 8" gas pipeline. Please refer to Topo D & D2.

The total liquid gathering pipeline distance from the separator to the tie in point is $\pm 985'$ and the individual segments are broken up as follows:

- $\pm 470'$ (0.09 miles) –New 6" buried liquid pipeline from the separator to the edge of the pad. Please refer to Topo D2 - Pad and Pipeline Detail.
- $\pm 515'$ (0.10 miles) –New 6" buried liquid pipeline from the edge of pad to the tie-in at the proposed 1022-12F Intersection 6" liquid pipeline. Please refer to Topo D & D2.

The liquid gathering lines will be made of polyethylene or a composite polyethylene/steel or polyethylene/fiberglass that is not subject to internal or external pipe corrosion. The content of the produced fluids to be transferred by the liquid gathering system will be approximately 92% produced water and 8% condensate. Trunk line valve connections for the water gathering system will be below ground but accessible from the surface in order to prevent freezing during winter time.

The proposed pipelines will be buried and will include gas gathering and liquid gathering pipelines in the same trench. Where the pipeline is adjacent to the road or well pad, the road and/or well pad will be utilized for construction activities and staging. KMG requests a permanent 30' right-of-way adjacent to the road for life-of-project for maintenance, repairs, and/or upgrades, no additional right-of-way will be needed beyond the 30'. Where the pipeline is not adjacent to the road or well pad, KMG requests a temporary 45' construction right-of-way 30' permanent right-of-way.

The proposed trench width for the pipeline would range from 18-48 inches and will be excavated to a depth of 48 to 60 inches of normal soil cover or 24 inches of cover in consolidated rock. During construction blasting may occur along the proposed right-of-way where trenching equipment cannot cut into the bedrock. Large debris and rocks removed from the earth during trenching and blasting that could not be returned to the trench would be distributed evenly and naturally in the project area. The proposed pipelines will be pressure tested pneumatically (depending on size) or with fluids (either fresh or produced). If fluids are used, there will be no discharge to the surface.

Pipeline signs will be installed along the right-of-way to indicate the pipeline proximity and ownership, as well as to provide emergency contact phone numbers. Above ground valves, T's, and/or cathodic protection will be installed at various locations for connection, corrosion prevention and/or for safety purposes.

D. Location and Type of Water Supply:

Water for drilling purposes will be obtained from one of the following sources:

NBU 1022-12E4CS/ 1022-12F4CS/
1022-12K1BS/ 1022-12K1CS
1022-12K4BS/ 1022-12K4CS

Surface Use Plan of Operations
4 of 9

- Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32 T4S R3E, Water User Claim number 43-8496, application number 53617.
- Price Water Pumping Inc. Green River and White River, various sources, Water Right Number 49-1659, application number: a35745.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

E. Source of Construction Materials:

Construction operations will typically be completed with native materials found on location. If needed, construction materials that must be imported to the site (mineral material aggregate, soils or materials suitable for fill/surfacing) will be obtained from a nearby permitted source and described in subsequent Sundry requests. No construction materials will be removed from State lands without prior approval from SITLA.

F. Methods for Handling Waste Materials:

Should the well be productive, produced water will be contained in a water tank and will be transported by pipeline and/or truck to an approved disposal sites facilities and/or Salt Water Disposal (SWD) injection well. Currently, those facilities are:

RNI in Sec. 5 T9S R22E
Ace Oilfield in Sec. 2 T6S R20E
MC&MC in Sec. 12 T6S R19E
Pipeline Facility in Sec. 36 T9S R20E
Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E
Bonanza Evaporation Pond in Sec. 2 T10S R23E
Ouray #1 SWD in Sec. 1 T9S R21E
NBU 159 SWD in Sec. 35 T9S R21E
CIGE 112D SWD in Sec. 19 T9S R21E
CIGE 114 SWD in Sec. 34 T9S R21E
NBU 921-34K SWD in Sec. 34 T9S R21E
NBU 921-33F SWD in Sec. 33 T9S R21E
NBU 921-34L SWD in Sec. 34 T9S R21E

Drill cuttings and/or fluids will be contained in the reserve/frac pit. Cuttings will be buried in pit(s) upon closure. Unless otherwise approved, no oil or other oil-based drilling additives, chromium/metals-based, or saline muds will be used during drilling. Only fresh water (as specified above), biodegradable polymer soap, bentonite clay, and/or non-toxic additives will be used in the mud system.

Pits will be constructed to minimize the accumulation of surface runoff. Should fluid hydrocarbons be encountered during drilling, completions or well testing, product will either be contained in test tanks on the well site or evacuated by vacuum trucks and transported to an approved disposal/sales facility. Should petroleum hydrocarbons unexpectedly

NBU 1022-12E4CS/ 1022-12F4CS/
1022-12K1BS/ 1022-12K1CS
1022-12K4BS/ 1022-12K4CS

Surface Use Plan of Operations
5 of 9

be released into a pit, they will be removed as soon as practical but in no case will they remain longer than 72 hours unless an alternate is approved by SITLA. Should timely removal prove infeasible, the pit will be netted with mesh no larger than 1 inch until such time as hydrocarbons can be removed. Hydrocarbon removal will also take place prior to the closure of the pit, unless authorization is provided for disposal via alternative pit closure methods (e.g. solidification.)

The reserve and/or fracture stimulation pit will be lined with a synthetic material 20 mil or thicker. The liner will be installed over smooth fill subgrade that is free of pockets, loose rocks, or other materials (i.e. sand, sifted dirt, bentonite, straw, etc.) that could damage the liner. Any additional pits necessary for subsequent operations, such as temporary flare or workover pits, will be contained within the originally approved well pad and disturbance boundaries. Such temporary pits will be backfilled and reclaimed within 180 days of completion of work at a well location.

For the protection of livestock and wildlife, all open pits and cellars will be fenced/covered to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

Pits containing drilling cuttings, mud, and/or completions fluids will be allowed to dry. Any free fluids remaining after six (6) months from reaching total depth, date of completion, and/or determination of inactivity will be removed (as weather conditions allow) to an approved site and the pit reclaimed. Additional drying methods may include fly-ash solidification or sprinkler evaporation. Installation and operation of any sprinklers, pumps, and equipment will ensure that water spray or mist does not drift. Reserve pit liners will be cut off or folded as near to the mud surface as possible and as safety considerations allow and buried on location.

No garbage or non-exempt substances as defined by Resource Conservation and Recovery Act (RCRA) subtitle C will be placed in the reserve pit. All refuse generated during construction, drilling, completion, and well testing activities will be contained in an enclosed receptacle, removed from the drill locations promptly, and transported to an approved disposal facility.

Portable, self-contained chemical toilets and/or sewage processing facilities will be provided for human waste disposal. Upon completion of operations, or as required, the toilet holding tanks will be pumped and the contents disposed of in an approved sewage disposal facility. All applicable regulations pertaining to disposal of human and solid waste will be observed.

Any undesirable event, including accidental release of fluids, or release in excess of reportable quantities, will be managed according to the notification requirements of UDOGMs "Reporting Oil and Gas Undesirable Events" rule. Where State wells are participatory to a Federal agreement, according to NTL-3A, the appropriate Federal agencies will be notified.

Materials Management

Hazardous materials above reportable quantities will not be produced by drilling or completing proposed wells or constructing the pipelines/facilities. The term "hazardous materials" as used here means: (1) any substance, pollutant, or containment listed as hazardous under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, as amended 42 U.S.C. 9601 et seq., and the regulations issued under CERCLA; and (2) any hazardous waste as defined in RCRA of 1976, as amended. In addition, no extremely hazardous substance, as defined in

NBU 1022-12E4CS/ 1022-12F4CS/
1022-12K1BS/ 1022-12K1CS
1022-12K4BS/ 1022-12K4CS

Surface Use Plan of Operations
6 of 9

40 CFR 355, in threshold planning quantities, would be used, produced, stored, transported, or disposed of while producing any well.

Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act (SARA) in quantities of 10,000 pounds or more may be produced and/or stored at production facilities and may be kept in limited quantities on drilling sites and well locations for short periods of time during drilling or completion activities.

G. Ancillary Facilities:

None are anticipated.

H. Well Site Layout (see Well Pad Design Summary):

The location, orientation and aerial extent of each drill pad; reserve/completion/flare pit; access road ingress/egress points, drilling rig, dikes/ditches, existing wells/infrastructure; proposed cuts and fills; and topsoil and spoil material stockpile locations are depicted on the exhibits for each project, where applicable. Site-specific conditions may require slight deviation in actual equipment and facility layout; however, the area of disturbance, as described in the survey, will not be exceeded.

Coordinates are provided in the National Spatial Reference System, North American Datum, 1927 (NAD27) or latest edition. Distances are depicted on each plat to the nearest two adjacent section lines.

I. Plans for Reclamation of the Surface:

Surface reclamation will be undertaken in two phases: interim and final. Interim reclamation is conducted following well completion and extends through the period of production. This reclamation is for the area of the well pad that is not required for production activities. Final reclamation is conducted following well plugging/conversion and/or facility abandonment processes.

Reclamation activities in both phases may include but is not limited to the re-contouring or re-configuration of topographic surfaces, restoration of drainage systems, segregation of spoils materials, minimizing surface disturbance, re-evaluating backfill requirements, pit closure, topsoil redistribution, soil treatments, seeding and weed control.

Interim Reclamation

Interim reclamation includes pit closure, re-contouring (where possible), soil bed preparation, topsoil placement, seeding, and/or weed control.

Interim re-contouring involves bringing all construction material from cuts and fills back onto the well pad and site and reestablishing the natural contours where desirable and practical. Fill and stockpiled spoils no longer necessary to the operation will be spread on the cut slopes and covered with stockpiled topsoil. All stockpiled top soils will be used for interim reclamation where practical to maintain soil viability. Where possible, the land surface will be left "rough" after re-contouring to ensure that the maximum surface area will be available to support the reestablishment of vegetative cover.

NBU 1022-12E4CS/ 1022-12F4CS/
1022-12K1BS/ 1022-12K1CS
1022-12K4BS/ 1022-12K4CS

Surface Use Plan of Operations
7 of 9

A reserve pit, upon being allowed to dry, will be backfilled and compacted with cover materials that are void of any topsoil, vegetation, large stones, rocks or foreign objects. Soils that are moisture laden, saturated, or partially/completely frozen will not be used for backfill or cover. The pit area will be mounded to allow for settling and to promote positive surface drainage away from the pit.

Final Reclamation

Final reclamation will be performed for newly drilled unproductive wells and/or at the end of the life of a productive well. As soon as practical after the conclusion of drilling and testing operations, unproductive drill holes will be plugged and abandoned (P&A). Site and road reclamation will commence following plugging. In no case will reclamation at non-producing locations be initiated later than six (6) months from the date a well is plugged. A joint inspection of the disturbed area to be reclaimed may be requested by KMG. The primary purpose of this inspection will be to review the existing conditions, or agree upon a revised final reclamation and abandonment plan. A Notice of Intent to Abandon will be filed for final recommendations regarding surface reclamation.

After plugging, all wellhead equipment that is no longer needed will be removed, and the well site will be reclaimed. Final contouring will blend with and follow as closely as practical the natural terrain and contours of the original site and surrounding areas. After re-contouring, final grading will be conducted over the entire surface of the well site and access road. Where practical, the area will be ripped to a depth of 18 to 24 inches on 18 to 24-inch centers and surface materials will be pitted with small depressions to form longitudinal depressions 12 to 18 inches deep perpendicular to the natural flow of water.

All unnecessary surface equipment and structures (e.g. cattle guards) and water control structures (e.g. culverts, drainage pipes) not needed to facilitate successful reclamation will be removed during final reclamation. Roads that will be reclaimed will be ripped to a depth of 18 inches where practical, re-contoured to approximate the original contour of the ground and seeded.

Upon successfully completing reclamation of a P&A location, a Final Abandonment Notice will be submitted to UDOGM.

Seeding and Measures Common to Interim and Final Reclamation

Reclaimed areas may be fenced to exclude grazing and encourage re-vegetation.

On slopes where severe erosion can become a problem and the use of machinery is not practical, seed will be hand broadcast and raked with twice the specified amount of seed. The slope will be stabilized using materials specifically designed to prevent erosion on steep slopes and hold seed in place so vegetation can become permanently established. These materials will include, but are not limited to, erosion control blankets and bonded fiber matrix at a rate to achieve a minimum of 80 percent soil coverage.

Seeding will occur year-round as conditions allow. Seed mixes appropriate to the native plant community as determined and specified for each project location based on the site specific soils will be used for re-vegetation. The site specific seed mix will be provided by SITLA.

NBU 1022-12E4CS/ 1022-12F4CS/
1022-12K1BS/ 1022-12K1CS
1022-12K4BS/ 1022-12K4CS

Surface Use Plan of Operations
8 of 9

J. Surface/Mineral Ownership:

SITLA
675 East 500 South, Suite 500
Salt Lake City, UT 84102

L. Other Information:

None

NBU 1022-12E4CS/ 1022-12F4CS/
1022-12K1BS/ 1022-12K1CS
1022-12K4BS/ 1022-12K4CS

Surface Use Plan of Operations
9 of 9

M. Lessee's or Operators' Representative & Certification:

Gina T. Becker
Regulatory Analyst II
Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779
(720) 929-6086

Tommy Thompson
General Manager, Drilling
Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779
(720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage for State lease activities is provided by State Surety Bond 22013542, and for applicable Federal lease activities and pursuant to 43 CFR 3104, by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.



Gina T. Becker

September 7, 2011

Date



Joseph D. Johnson
1099 18TH STREET STE. 1800 • DENVER, CO
80202
720-929-6708 • FAX 720-929-7708
E-MAIL: JOE.JOHNSON@ANADARKO.COM

September 7, 2011

Ms. Diana Mason
Division of Oil, Gas and Mining
P.O. Box 145801
Salt Lake City, UT 84114-6100

Re: Directional Drilling R649-3-11
NBU 1022-12K1BS
10S-22E-Sec. 12
SEWN/NESW
Surface: 2473' FNL, 2359' FWL
Bottom Hole: 2567' FSL, 2142' FWL
Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to the Exception to Location and Siting of Wells.

- Kerr-McGee's NBU 1022-12K1BS is located within the Natural Buttes Unit area.
- Kerr-McGee is permitting this well as a directional well in order to minimize surface disturbance. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to utilize the existing road and pipelines in the area.
- Furthermore, Kerr-McGee certifies that it is the sole working interest owner within 460 feet of the entire directional well bore.

Therefore, based on the above stated information Kerr-McGee Oil & Gas Onshore LP requests the permit be granted pursuant to R649-3-11.


Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

A handwritten signature in blue ink, appearing to read 'JDJ', with a horizontal line underneath.



Joseph D. Johnson
Landman

RECEIVED: September 13, 2011



API Number: 4304751965
Well Name: NBU 1022-12K1BS
Township T1.0 Range R2.2 Section 12
Meridian: SLBM
Operator: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Map Prepared:
Map Produced by Diana Mason



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

3160

(UT-922)

September 19, 2011

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2011 Plan of Development Natural Buttes Unit
Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2011 within the Natural Buttes Unit, Uintah County, Utah.

API #	WELL NAME	LOCATION
-------	-----------	----------

(Proposed PZ WASATCH-MESA VERDE)

NBU 1022-12H PAD

43-047-51941	NBU 1022-12H4BS	Sec 12 T10S R22E 1846 FNL 0361 FEL
	BHL	Sec 12 T10S R22E 2071 FNL 0491 FEL

43-047-51942	NBU 1022-12H1CS	Sec 12 T10S R22E 1843 FNL 0341 FEL
	BHL	Sec 12 T10S R22E 1740 FNL 0491 FEL

43-047-51973	NBU 1022-12H1BS	Sec 12 T10S R22E 1842 FNL 0331 FEL
	BHL	Sec 12 T10S R22E 1408 FNL 0491 FEL

43-047-51975	NBU 1022-12H4CS	Sec 12 T10S R22E 1845 FNL 0351 FEL
	BHL	Sec 12 T10S R22E 2402 FNL 0492 FEL

NBU 1022-12O PAD

43-047-51943	NBU 1022-12N4BS	Sec 12 T10S R22E 1224 FSL 2329 FEL
	BHL	Sec 12 T10S R22E 0580 FSL 2150 FWL

43-047-51945	NBU 1022-12N4CS	Sec 12 T10S R22E 1216 FSL 2323 FEL
	BHL	Sec 12 T10S R22E 0251 FSL 2141 FWL

43-047-51956	NBU 1022-12J4CS	Sec 12 T10S R22E 1240 FSL 2341 FEL
	BHL	Sec 12 T10S R22E 1409 FSL 1817 FEL

43-047-51959	NBU 1022-12N1BS	Sec 12 T10S R22E 1257 FSL 2352 FEL
	BHL	Sec 12 T10S R22E 1242 FSL 2147 FWL

43-047-51960	NBU 1022-12J4BS	Sec 12 T10S R22E 1249 FSL 2346 FEL
	BHL	Sec 12 T10S R22E 1740 FSL 1816 FEL

RECEIVED: September 20, 2011

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
43-047-51961	NBU 1022-12N1CS	Sec 12 T10S R22E 1232 FSL 2335 FEL
	BHL	Sec 12 T10S R22E 0911 FSL 2149 FWL
NBU 1022-12B PAD		
43-047-51944	NBU 1022-12B1BS	Sec 12 T10S R22E 0668 FNL 2232 FEL
	BHL	Sec 12 T10S R22E 0259 FNL 1797 FEL
43-047-51979	NBU 1022-12C1BS	Sec 12 T10S R22E 0651 FNL 2244 FEL
	BHL	Sec 12 T10S R22E 0089 FNL 2138 FWL
43-047-51980	NBU 1022-12B1CS	Sec 12 T10S R22E 0676 FNL 2227 FEL
	BHL	Sec 12 T10S R22E 0579 FNL 1806 FEL
43-047-51981	NBU 1022-12C1CS	Sec 12 T10S R22E 0660 FNL 2238 FEL
	BHL	Sec 12 T10S R22E 0414 FNL 2133 FWL
43-047-51982	NBU 1022-12B4BS	Sec 12 T10S R22E 0684 FNL 2221 FEL
	BHL	Sec 12 T10S R22E 0910 FNL 1807 FEL
43-047-51983	NBU 1022-12B4CS	Sec 12 T10S R22E 0692 FNL 2215 FEL
	BHL	Sec 12 T10S R22E 1241 FNL 1808 FEL
NBU 1022-12P PAD		
43-047-51947	NBU 1022-12P4CS	Sec 12 T10S R22E 1115 FSL 0442 FEL
	BHL	Sec 12 T10S R22E 0246 FSL 0491 FEL
43-047-51962	NBU 1022-12I4CS	Sec 12 T10S R22E 1112 FSL 0451 FEL
	BHL	Sec 12 T10S R22E 1574 FSL 0493 FEL
43-047-51968	NBU 1022-12P1BS	Sec 12 T10S R22E 1109 FSL 0461 FEL
	BHL	Sec 12 T10S R22E 1240 FSL 0489 FEL
43-047-51969	NBU 1022-12P4BS	Sec 12 T10S R22E 1105 FSL 0470 FEL
	BHL	Sec 12 T10S R22E 0580 FSL 0494 FEL
NBU 1022-12P2 PAD		
43-047-51949	NBU 1022-12O1BS	Sec 12 T10S R22E 0877 FSL 1322 FEL
	BHL	Sec 12 T10S R22E 1077 FSL 1818 FEL
43-047-51950	NBU 1022-12O1CS	Sec 12 T10S R22E 0873 FSL 1331 FEL
	BHL	Sec 12 T10S R22E 0761 FSL 1834 FEL
43-047-51953	NBU 1022-12O4BS	Sec 12 T10S R22E 0881 FSL 1313 FEL
	BHL	Sec 12 T10S R22E 0415 FSL 1820 FEL
43-047-51954	NBU 1022-12O4CS	Sec 12 T10S R22E 0885 FSL 1304 FEL
	BHL	Sec 12 T10S R22E 0082 FSL 1828 FEL
NBU 1022-12A PAD		
43-047-51951	NBU 1022-12A1BS	Sec 12 T10S R22E 0598 FNL 0621 FEL
	BHL	Sec 12 T10S R22E 0081 FNL 0481 FEL
43-047-51952	NBU 1022-12A1CS	Sec 12 T10S R22E 0591 FNL 0592 FEL
	BHL	Sec 12 T10S R22E 0414 FNL 0490 FEL

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
43-047-51986	NBU 1022-12A4CS	Sec 12 T10S R22E 0596 FNL 0611 FEL
	BHL	Sec 12 T10S R22E 1077 FNL 0491 FEL
43-047-51991	NBU 1022-12A4BS	Sec 12 T10S R22E 0593 FNL 0601 FEL
	BHL	Sec 12 T10S R22E 0746 FNL 0490 FEL
NBU 1022-12I PAD		
43-047-51955	NBU 1022-12J1CS	Sec 12 T10S R22E 2333 FSL 1011 FEL
	BHL	Sec 12 T10S R22E 2071 FSL 1815 FEL
43-047-51957	NBU 1022-12J1BS	Sec 12 T10S R22E 2337 FSL 1002 FEL
	BHL	Sec 12 T10S R22E 2402 FSL 1814 FEL
43-047-51958	NBU 1022-12I4BS	Sec 12 T10S R22E 2341 FSL 0993 FEL
	BHL	Sec 12 T10S R22E 1905 FSL 0493 FEL
43-047-51976	NBU 1022-12I1BS	Sec 12 T10S R22E 2350 FSL 0974 FEL
	BHL	Sec 12 T10S R22E 2568 FSL 0492 FEL
43-047-51978	NBU 1022-12I1CS	Sec 12 T10S R22E 2345 FSL 0984 FEL
	BHL	Sec 12 T10S R22E 2237 FSL 0492 FEL
NBU 1022-12G PAD		
43-047-51963	NBU 1022-12G1CS	Sec 12 T10S R22E 1833 FNL 1721 FEL
	BHL	Sec 12 T10S R22E 1904 FNL 1810 FEL
43-047-51972	NBU 1022-12G4BS	Sec 12 T10S R22E 1841 FNL 1715 FEL
	BHL	Sec 12 T10S R22E 2235 FNL 1812 FEL
43-047-51974	NBU 1022-12G1BS	Sec 12 T10S R22E 1826 FNL 1727 FEL
	BHL	Sec 12 T10S R22E 1572 FNL 1809 FEL
43-047-51977	NBU 1022-12G4CS	Sec 12 T10S R22E 1849 FNL 1709 FEL
	BHL	Sec 12 T10S R22E 2566 FNL 1813 FEL
NBU 1022-12F4 PAD		
43-047-51964	NBU 1022-12F4CS	Sec 12 T10S R22E 2462 FNL 2342 FWL
	BHL	Sec 12 T10S R22E 2401 FNL 2141 FWL
43-047-51965	NBU 1022-12K1BS	Sec 12 T10S R22E 2473 FNL 2359 FWL
	BHL	Sec 12 T10S R22E 2567 FSL 2142 FWL
43-047-51966	NBU 1022-12K1CS	Sec 12 T10S R22E 2479 FNL 2367 FWL
	BHL	Sec 12 T10S R22E 2236 FSL 2144 FWL
43-047-51967	NBU 1022-12E4CS	Sec 12 T10S R22E 2467 FNL 2350 FWL
	BHL	Sec 12 T10S R22E 2565 FNL 0822 FWL
43-047-51970	NBU 1022-12K4BS	Sec 12 T10S R22E 2484 FNL 2375 FWL
	BHL	Sec 12 T10S R22E 1904 FSL 2145 FWL
43-047-51971	NBU 1022-12K4CS	Sec 12 T10S R22E 2490 FNL 2384 FWL
	BHL	Sec 12 T10S R22E 1573 FSL 2146 FWL

API #	WELL NAME	LOCATION
-------	-----------	----------

(Proposed PZ WASATCH-MESA VERDE)

NBU 1022-12CPAD

43-047-51984	NBU 1022-12C4BS	Sec 12 T10S R22E 0827 FNL 2020 FWL
	BHL	Sec 12 T10S R22E 0745 FNL 2134 FWL

43-047-51985	NBU 1022-12C4CS	Sec 12 T10S R22E 0855 FNL 2031 FWL
	BHL	Sec 12 T10S R22E 1076 FNL 2135 FWL

43-047-51987	NBU 1022-12D1CS	Sec 12 T10S R22E 0818 FNL 2016 FWL
	BHL	Sec 12 T10S R22E 0579 FNL 0819 FWL

43-047-51989	NBU 1022-12D1BS	Sec 12 T10S R22E 0809 FNL 2013 FWL
	BHL	Sec 12 T10S R22E 0260 FNL 0823 FWL

43-047-51990	NBU 1022-12D4BS	Sec 12 T10S R22E 0837 FNL 2024 FWL
	BHL	Sec 12 T10S R22E 0910 FNL 0819 FWL

43-047-51992	NBU 1022-12D4CS	Sec 12 T10S R22E 0846 FNL 2027 FWL
	BHL	Sec 12 T10S R22E 1241 FNL 0820 FWL

NBU 1022-12FPAD

43-047-51988	NBU 1022-12E1BS	Sec 12 T10S R22E 1818 FNL 2146 FWL
	BHL	Sec 12 T10S R22E 1572 FNL 0820 FWL

43-047-51993	NBU 1022-12E1CS	Sec 12 T10S R22E 1824 FNL 2154 FWL
	BHL	Sec 12 T10S R22E 1903 FNL 0821 FWL

43-047-51994	NBU 1022-12E4BS	Sec 12 T10S R22E 1835 FNL 2170 FWL
	BHL	Sec 12 T10S R22E 2234 FNL 0821 FWL

43-047-51995	NBU 1022-12F4BS	Sec 12 T10S R22E 1847 FNL 2187 FWL
	BHL	Sec 12 T10S R22E 2070 FNL 2140 FWL

43-047-51996	NBU 1022-12F1BS	Sec 12 T10S R22E 1841 FNL 2179 FWL
	BHL	Sec 12 T10S R22E 1407 FNL 2137 FWL

43-047-51997	NBU 1022-12F1CS	Sec 12 T10S R22E 1830 FNL 2162 FWL
	BHL	Sec 12 T10S R22E 1739 FNL 2138 FWL

Michael L. Coulthard

Digitally signed by Michael L. Coulthard
 DN: cn=Michael L. Coulthard, o=Bureau of Land Management, ou=Branch of Minerals,
 email=Michael_Coulthard@blm.gov, c=US
 Date: 2011.09.19 14:47:24 -0600

bcc: File - Natural Buttes Unit

Division of Oil Gas and Mining

Central Files

Agr. Sec. Chron

Fluid Chron

MCoulthard:mc:9-19-11

RECEIVED: September 20, 2011

From: Diana Mason
To:
Subject: Fwd: Kerr McGee APD approvals

The following APDs have been approved by SITLA including arch and paleo clearance.

NBU 1022-12A1BS (4304751951)
NBU 1022-12A1CS (4304751952)
NBU 1022-12A4CS (4304751986)
)NBU 1022-12A4BS (4304751991)
NBU 1022-12J1CS (4304751955)
NBU 1022-12J1BS (4304751957)
NBU 1022-12I4BS (4304751958)
NBU 1022-12I1BS (4304751976)
NBU 1022-12I1CS (4304751978)
NBU 1022-12B1BS (4304751944)
)NBU 1022-12C1BS (4304751979)
NBU 1022-12B1CS (4304751980)
)NBU 1022-12C1CS (4304751981)
NBU 1022-12B4BS (4304751982)
NBU 1022-12B4CS (4304751983)
)NBU 1022-12H4BS (4304751941)
NBU 1022-12H1CS (4304751942)
NBU 1022-12H1BS (4304751973)
NBU 1022-12H4CS (4304751975)
NBU 1022-12F4CS (4304751964)
NBU 1022-12K1BS (4304751965)
NBU 1022-12K1CS (4304751966)
NBU 1022-12E4CS (4304751967)
NBU 1022-12K4BS (4304751970)
NBU 1022-12K4CS (4304751971)
NBU 1022-12O1BS (4304751949)
NBU 1022-12O1CS (4304751950)
NBU 1022-12O4BS (4304751953)
NBU 1022-12O4CS (4304751954)
NBU 1022-12P4CS (4304751947)
NBU 1022-12I4CS (4304751962)
NBU 1022-12P1BS (4304751968)
NBU 1022-12P4BS (4304751969)
NBU 1022-12G1CS (4304751963)
NBU 1022-12G4BS (4304751972)
NBU 1022-12G1BS (4304751974)
NBU 1022-12G4CS (4304751977)
NBU 1022-12N4BS (4304751943)
NBU 1022-12N4CS (4304751945)
NBU 1022-12J4CS (4304751956)
NBU 1022-12N1BS (4304751959)
NBU 1022-12J4BS (4304751960)
NBU 1022-12N1CS (4304751961)

-Jim Davis

RECEIVED: November 08, 2011

Jim Davis
Utah Trust Lands Administration
jimdavis1@utah.gov
Phone: (801) 538-5156

Well Name	KERR-MCGEE OIL & GAS ONSHORE, L.P. NBU 1022-12K1B			
String	Surf	Prod		
Casing Size(in)	8.625	4.500		
Setting Depth (TVD)	2151	8454		
Previous Shoe Setting Depth (TVD)	40	2151		
Max Mud Weight (ppg)	8.3	12.5		
BOPE Proposed (psi)	500	5000		
Casing Internal Yield (psi)	3390	7780		
Operators Max Anticipated Pressure (psi)	5411	12.3		

Calculations	Surf String	8.625	"	
Max BHP (psi)	.052*Setting Depth*MW=	928		
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	670	NO	air drill
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	455	YES	OK
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	464	NO	Reasonable for area
Required Casing/BOPE Test Pressure=		2151	psi	
*Max Pressure Allowed @ Previous Casing Shoe=		40	psi *Assumes 1psi/ft frac gradient	

Calculations	Prod String	4.500	"	
Max BHP (psi)	.052*Setting Depth*MW=	5495		
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	4481	YES	
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	3635	YES	OK
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	4108	NO	Reasonable
Required Casing/BOPE Test Pressure=		5000	psi	
*Max Pressure Allowed @ Previous Casing Shoe=		2151	psi *Assumes 1psi/ft frac gradient	

Calculations	String		"	
Max BHP (psi)	.052*Setting Depth*MW=			
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO	
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO	
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO	
Required Casing/BOPE Test Pressure=			psi	
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient	

Calculations	String		"	
Max BHP (psi)	.052*Setting Depth*MW=			
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO	
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO	
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO	
Required Casing/BOPE Test Pressure=			psi	


API Well Number: 43047519650000

*Max Pressure Allowed @ Previous Casing Shoe=

psi *Assumes 1psi/ft frac gradient

43047519650000 NBU 1022-12K1BS

Casing Schematic



Well name:	43047519650000 NBU 1022-12K1BS	
Operator:	KERR-MCGEE OIL & GAS ONSHORE, L.P.	
String type:	Surface	Project ID: 43-047-51965
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 8.330 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 104 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 1,062 ft

Burst

Max anticipated surface pressure: 1,910 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 2,168 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 1,903 ft

Directional Info - Build & Drop

Kick-off point 300 ft
Departure at shoe: 257 ft
Maximum dogleg: 2 °/100ft
Inclination at shoe: 9 °

Re subsequent strings:

Next setting depth: 8,478 ft
Next mud weight: 12.500 ppg
Next setting BHP: 5,505 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 2,170 ft
Injection pressure: 2,170 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	2170	8.625	28.00	I-55	LT&C	2151	2170	7.892	85932

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	931	1880	2.020	2168	3390	1.56	60.2	348	5.78 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: November 21, 2011
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 2151 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	43047519650000 NBU 1022-12K1BS	
Operator:	KERR-MCGEE OIL & GAS ONSHORE, L.P.	
String type:	Production	Project ID: 43-047-51965
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 12.500 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 192 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 770 ft

Burst

Max anticipated surface pressure: 3,630 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 5,490 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Directional Info - Build & Drop

Kick-off point 300 ft
Departure at shoe: 326 ft
Maximum dogleg: 2 °/100ft
Inclination at shoe: 0 °

Tension is based on air weight.

Neutral point: 6,898 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	8478	4.5	11.60	I-80	LT&C	8454	8478	3.875	111910
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	5490	6360	1.159	5490	7780	1.42	98.1	212	2.16 J

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: November 21, 2011
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 8454 ft, a mud weight of 12.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator	KERR-MCGEE OIL & GAS ONSHORE, L.P.				
Well Name	NBU 1022-12K1BS				
API Number	43047519650000	APD No	4592	Field/Unit	NATURAL BUTTES
Location: 1/4,1/4	SENW	Sec	12	Tw	10.0S
		Rng	22.0E	2473	FNL 2359 FWL
GPS Coord (UTM)	637625	4424789	Surface Owner		

Participants

Andy Lytle, Sheila Wopsock, Charles Chase, Grizz Oleen, Jaime Scharnowski, Doyle Holmes, (Kerr McGee). John Slauch, Mitch Batty, (Timberline). Jim Davis (SITLA). Ben Williams (DWR). David Hackford, (DOGM).

Regional/Local Setting & Topography

The general area is in the southeast portion of the Natural Buttes Unit. Within this area is the White River and rugged drainages that drain into it. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River is approx. 0.3 miles to the west. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 47.3 miles to the northwest. Access from Vernal is by following Utah State, Uintah County and oilfield development roads. Five wells, in addition to this one (for a total of six) will be directionally drilled from this pad. This proposed location will be a new pad. A 610' new access road will be constructed. The proposed location will run in a northwest-southeast direction on the top of a flat topped ridge. This ridge breaks off sharply into rugged secondary canyons especially to the south. The reserve pit will be on the south corner of the location and the excess cut stockpiles will be on the west, north and south sides of the location. The north corner of the location will be compacted fill. The pad should be stable and should be a suitable location for six wells, and is on the best site available in the immediate area.

Surface Use Plan

Current Surface Use

Grazing
Wildlife Habitat

New Road Miles	Well Pad	Src Const Material	Surface Formation
0.11	Width 352 Length 425	Onsite	UNTA

Ancillary Facilities N

Waste Management Plan Adequate? Y

Environmental Parameters

Affected Floodplains and/or Wetlands N

Flora / Fauna

Prickly pear, wild onion, shadscale, mat saltbrush, Indian ricegrass, halogeton, pepper grass, annuals and curly Vegetation is a salt desert shrub type. Principal species present are cheatgrass, black sagebrush, stipa, mesquite grass.

Sheep, antelope, coyote, raptors, small mammals and birds.

Soil Type and Characteristics

Rocky sandy clay loam.

Erosion Issues N**Sedimentation Issues** N**Site Stability Issues** Y

North corner of location will be 7.4 feet of fill. This must be compacted during location construction.

Drainage Diversion Required? N**Berm Required?** N**Erosion Sedimentation Control Required?** N**Paleo Survey Run?** Y **Paleo Potential Observed?** N **Cultural Survey Run?** Y **Cultural Resources?** N**Reserve Pit****Site-Specific Factors****Site Ranking**

Distance to Groundwater (feet)	100 to 200	5
Distance to Surface Water (feet)	>1000	0
Dist. Nearest Municipal Well (ft)	>5280	0
Distance to Other Wells (feet)		20
Native Soil Type	High permeability	20
Fluid Type	Fresh Water	5
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)		0
Affected Populations		
Presence Nearby Utility Conduits	Not Present	0
Final Score		50

1 Sensitivity Level

Characteristics / Requirements

The reserve pit is planned in an area of cut on the south corner of the location. Dimensions are 120' x 260' x 12' deep with two feet of freeboard. Kerr McGee has agreed to line this pit with a 16 mil synthetic liner and a layer of felt sub-liner.

Closed Loop Mud Required? N **Liner Required?** Y **Liner Thickness** 16 **Pit Underlayment Required?** Y**Other Observations / Comments**

There is an unused water well 300' north of this site.

David Hackford
Evaluator

10/12/2011
Date / Time

Application for Permit to Drill

Statement of Basis

12/12/2011

Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
4592	43047519650000	SITLA	GW	S	No
Operator	KERR-MCGEE OIL & GAS ONSHORE, L.P.		Surface Owner-APD		
Well Name	NBU 1022-12K1BS		Unit	NATURAL BUTTES	
Field	NATURAL BUTTES		Type of Work	DRILL	
Location	SENW 12 10S 22E S 2473 FNL 2359 FWL GPS Coord (UTM) 637556E 4424994N				

Geologic Statement of Basis

Kerr McGee proposes to set 2,170' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 4,000'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 12. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Production casing cement should be brought up above the base of the moderately saline ground water to isolate it from fresher waters uphole.

 Brad Hill
APD Evaluator

 11/2/2011
Date / Time
Surface Statement of Basis

The general area is in the southeast portion of the Natural Buttes Unit. Within this area is the White River and rugged drainages that drain into it. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River is 0.3 miles to the east. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 47.3 miles to the northwest. Access from Vernal is by following Utah State, Uintah County and oilfield development roads. A 610' new access road will be constructed.

Six wells will be directionally drilled from this location. They are the NBU 1022-12E4CS, NBU 1022-12F4CS, NBU 1022-12K1BS, NBU 1022-12K1CS, NBU 1022-12K4BS and the NBU 1022-12K4CS. The proposed location is on the point of a flat topped ridge that runs in a north-south direction. This ridge breaks off sharply into rugged secondary canyons especially to the south. The pad as constructed should be stable and sufficient for six wells, and is the best site in the immediate area.

Excess material will be stockpiled on the west and east sides of the location. The north corner of the location will be fill and will be compacted during location construction.

Both the surface and minerals are owned by SITLA. Jim Davis of SITLA and Ben Williams with DWR were invited by email to the pre-site evaluation. Both were present. Kerr McGee was told to consult with SITLA for reclamation standards including seeding mixes to be used.

 David Hackford
Onsite Evaluator

 10/12/2011
Date / Time
Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Pits	The reserve pit should be located on the south side of the location.

RECEIVED: December 12, 2011

**Application for Permit to Drill
Statement of Basis**

12/12/2011

Utah Division of Oil, Gas and Mining

Page 2

Surface

The well site shall be bermed to prevent fluids from leaving the pad.

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 9/13/2011**API NO. ASSIGNED:** 43047519650000**WELL NAME:** NBU 1022-12K1BS**OPERATOR:** KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995)**PHONE NUMBER:** 720 929-6086**CONTACT:** Gina Becker**PROPOSED LOCATION:** SENW 12 100S 220E**Permit Tech Review:** ☒**SURFACE:** 2473 FNL 2359 FWL**Engineering Review:** ☒**BOTTOM:** 2567 FSL 2142 FWL**Geology Review:** ☒**COUNTY:** UINTAH**LATITUDE:** 39.96391**LONGITUDE:** -109.38940**UTM SURF EASTINGS:** 637556.00**NORTHINGS:** 4424994.00**FIELD NAME:** NATURAL BUTTES**LEASE TYPE:** 3 - State**LEASE NUMBER:** UT ST UO 01997-A ST**PROPOSED PRODUCING FORMATION(S):** WASATCH-MESA VERDE**SURFACE OWNER:** 3 - State**COALBED METHANE:** NO**RECEIVED AND/OR REVIEWED:**☒ **PLAT**☒ **Bond:** STATE/FEE - 22013542☐ **Potash**☒ **Oil Shale 190-5**☐ **Oil Shale 190-3**☐ **Oil Shale 190-13**☒ **Water Permit:** 43-8496☐ **RDCC Review:**☐ **Fee Surface Agreement**☒ **Intent to Commingle****Commingle Approved****LOCATION AND SITING:**☐ **R649-2-3.****Unit:** NATURAL BUTTES☐ **R649-3-2. General**☐ **R649-3-3. Exception**☒ **Drilling Unit****Board Cause No:** Cause 173-14**Effective Date:** 12/2/1999**Siting:** Suspends General Siting☒ **R649-3-11. Directional Drill****Comments:** Presite Completed

Stipulations: 3 - Commingle - ddoucet
5 - Statement of Basis - bhill
15 - Directional - dmason
17 - Oil Shale 190-5(b) - dmason
25 - Surface Casing - hmadonald

RECEIVED: December 12, 2011



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: NBU 1022-12K1BS

API Well Number: 43047519650000

Lease Number: UT ST UO 01997-A ST

Surface Owner: STATE

Approval Date: 12/12/2011

Issued to:

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the WASATCH-MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Commingling:

In accordance with Board Cause No. 173-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Surface casing shall be cemented to the surface.

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan – contact Dustin Doucet
- Significant plug back of the well – contact Dustin Doucet
- Plug and abandonment of the well – contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program – contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well – contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

Approved By:



For John Rogers
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UT ST UO 01997-
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 1022-12K1BS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2473 FNL 2359 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 12 Township: 10.0S Range: 22.0E Meridian: S		9. API NUMBER: 43047519650000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 4/6/2012	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU TRIPLE A BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" 36.7# SCHEDULE 10 CONDUCTOR PIPE. CEMENT WITH 28 SACKS READY MIX. SPUD WELL LOCATION ON APRIL 6, 2012 AT 16:00 HRS.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY April 17, 2012		
NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBER 720 929-6304	TITLE Regularatory Analyst
SIGNATURE N/A	DATE 4/11/2012	

BLM - Vernal Field Office - Notification Form

Operator KERR-McGEE OIL & GAS Rig Name/# BUCKET RIG
Submitted By JAIME SCHARNOWSKE Phone Number 720.929.6304
Well Name/Number NBU 1022-12K1BS
Qtr/Qtr SEnw Section 12 Township 10S Range 22E
Lease Serial Number UT ST UO 01997-A ST
API Number 4304751965

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 04/06/2012 08:00 HRS AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☒ Surface Casing
☐ Intermediate Casing
☐ Production Casing
☐ Liner
☐ Other

RECEIVED

APR 03 2012

DIV. OF OIL, GAS & MINING

Date/Time 04/14/2012 08:00 HRS AM ☐ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point
☐ BOPE test at intermediate casing point
☐ 30 day BOPE test
☐ Other

Date/Time _____ AM ☐ PM ☐

Remarks ESTIMATED DATE AND TIME. PLEASE CONTACT KENNY GATHINGS AT
435.828.0986 OR LOVEL YOUNG AT 435.781.7051

BLM - Vernal Field Office - Notification Form

Operator KERR-McGEE OIL & GAS Rig Name/# BUCKET RIG
Submitted By JAIME SCHARNOWSKE Phone Number 720.929.6304
Well Name/Number NBU 1022-12K1BS
Qtr/Qtr SEnw Section 12 Township 10S Range 22E
Lease Serial Number UT ST UO 01997-A ST
API Number 4304751965

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 04/06/2012 08:00 HRS AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☒ Surface Casing
☐ Intermediate Casing
☐ Production Casing
☐ Liner
☐ Other

RECEIVED

APR 03 2012

DIV. OF OIL, GAS & MINING

Date/Time 04/14/2012 08:00 HRS AM ☐ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point
☐ BOPE test at intermediate casing point
☐ 30 day BOPE test
☐ Other

Date/Time _____ AM ☐ PM ☐

Remarks ESTIMATED DATE AND TIME. PLEASE CONTACT KENNY GATHINGS AT
435.828.0986 OR LOVEL YOUNG AT 435.781.7051

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: KERR MCGEE OIL & GAS ONSHORE LP Operator Account Number: N 2995
Address: P.O. Box 173779
City Denver
State CO Zip 80217 Phone Number: (720) 929-6304

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304751965	NBU 1022-12K1BS		SEnw	12	10S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
B	999999	2900	4/6/2012		4/24/2012		
Comments: MIRU BUCKET RIG SPUD WELL LOCATION ON 4/6/2012 AT 16:00 HOURS. <i>wsmd</i> <i>BHL new</i>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304751967	NBU 1022-12E4CS		SEnw	12	10S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
B	999999	2900	4/7/2012		4/24/2012		
Comments: MIRU BUCKET RIG SPUD WELL LOCATION ON 4/7/2012 AT 09:00 HOURS. <i>wsmd</i> <i>BHL: swnw</i>							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304751964	NBU 1022-12F4CS		SEnw	12	10S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
B	999999	2900	4/7/2012		4/24/2012		
Comments: MIRU BUCKET RIG SPUD WELL LOCATION ON 4/7/2012 AT 12:30 HOURS. <i>wsmd</i> <i>BHL: senw</i>							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

JAIME SCHARNOWSKE

Name (Please Print) *Jaime Scharnowske*

Signature
REGULATORY ANALYST 4/11/2012
Title Date

RECEIVED
APR 11 2012

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UT ST UO 01197-
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 1022-12K1BS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2473 FNL 2359 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 12 Township: 10.0S Range: 22.0E Meridian: S		9. API NUMBER: 43047519650000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 4/26/2012	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU AIR RIG ON 4/24/2012. DRILLED SURFACE HOLE TO 2295'. RAN SURFACE CASING AND CEMENTED. WELL IS WAITING ON ROTARY RIG. DETAILS OF CEMENT JOB WILL BE INCLUDED WITH WELL COMPLETION REPORT.		
NAME (PLEASE PRINT) Gina Becker		PHONE NUMBER 720 929-6086
SIGNATURE N/A		TITLE Regulatory Analyst II
DATE 4/26/2012		<div style="text-align: right;"> Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY May 02, 2012 </div>

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:

UT ST UO 01197-A ST

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

UTU63047A

1. TYPE OF WELL

OIL WELL ☐

GAS WELL ☒

OTHER _____

8. WELL NAME and NUMBER:

Multiple Well Locations

2. NAME OF OPERATOR:

Kerr-McGee Oil & Gas Onshore, L.P.

9. API NUMBER:

3. ADDRESS OF OPERATOR:

P.O. Box 173779

Denver

CO

80217

PHONE NUMBER:

(720) 929-6086

10. FIELD AND POOL, OR WILDCAT

Natural Buttes

4. LOCATION OF WELL

FOOTAGES AT SURFACE: Various Locations in T10S-R22E, Section 12

COUNTY: Uintah

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

12 10S 22E 6

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>4/23/2012</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>Lease Number</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<u>Correction</u>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Kerr-McGee is requesting approval to correct the lease number from UT ST UO 01997-A ST to UT ST UO 01197-A ST for various well locations. Please see attached well list.

Thank you!

NAME (PLEASE PRINT) Gina T Becker

TITLE Senior Regulatory Analyst

SIGNATURE 

DATE 4/23/2012

(This space for State use only)

RECEIVED

APR 24 2012

	API UWI NO	WELL NAME	SL STATE	SL SECTION	SL TOWNSHIP	SL RANGE	SL COUNTY NAME	GOV LEASE NO	FEDERAL LEASE NO
1	4304751951	NBU 1022-12A1BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
2	4304751952	NBU 1022-12A1CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
3	4304751991	NBU 1022-12A4BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
4	4304751986	NBU 1022-12A4CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
5	4304751944	NBU 1022-12B1BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
6	4304751980	NBU 1022-12B1CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
7	4304751982	NBU 1022-12B4BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
8	4304751983	NBU 1022-12B4CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
9	4304751979	NBU 1022-12C1BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
10	4304751981	NBU 1022-12C1CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
11	4304751984	NBU 1022-12C4BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
12	4304751985	NBU 1022-12C4CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
13	4304751989	NBU 1022-12D1BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
14	4304751987	NBU 1022-12D1CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
15	4304751990	NBU 1022-12D4BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
16	4304751992	NBU 1022-12D4CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
17	4304751988	NBU 1022-12E1BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
18	4304751993	NBU 1022-12E1CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
19	4304751994	NBU 1022-12E4BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
20	4304751996	NBU 1022-12F1BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
21	4304751997	NBU 1022-12F1CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
22	4304751995	NBU 1022-12F4BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
23	4304751967	NBU 1022-12E4CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
24	4304751964	NBU 1022-12F4CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
25	4304751965	NBU 1022-12K1BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
26	4304751966	NBU 1022-12K1CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
27	4304751970	NBU 1022-12K4BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
28	4304751971	NBU 1022-12K4CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
29	4304751974	NBU 1022-12G1BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
30	4304751963	NBU 1022-12G1CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
31	4304751972	NBU 1022-12G4BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
32	4304751977	NBU 1022-12G4CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
33	4304751973	NBU 1022-12H1BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
34	4304751942	NBU 1022-12H1CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
35	4304751941	NBU 1022-12H4BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
36	4304751975	NBU 1022-12H4CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
37	4304751976	NBU 1022-12I1BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
38	4304751978	NBU 1022-12I1CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
39	4304751958	NBU 1022-12I4BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
40	4304751957	NBU 1022-12J1BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
41	4304751955	NBU 1022-12J1CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
42	4304751960	NBU 1022-12J4BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
43	4304751956	NBU 1022-12J4CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
44	4304751959	NBU 1022-12N1BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
45	4304751961	NBU 1022-12N1CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
46	4304751943	NBU 1022-12N4BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
47	4304751945	NBU 1022-12N4CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
48	4304751962	NBU 1022-12I4CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
49	4304751968	NBU 1022-12P1BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A

	API UWI NO	WELL NAME	SL STATE	SL SECTION	SL TOWNSHIP	SL RANGE	SL COUNTY NAME	GOV LEASE NO	FEDERAL LEASE NO
50	4304751969	NBU 1022-12P4BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
51	4304751947	NBU 1022-12P4CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
52	4304751949	NBU 1022-12O1BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
53	4304751950	NBU 1022-12O1CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
54	4304751953	NBU 1022-12O4BS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A
55	4304751954	NBU 1022-12O4CS	UT	12	10	22	UINTAH	UT ST UO 01197-A ST	UTU63047A

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UT ST UO 01197-
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 1022-12K1BS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2473 FNL 2359 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 12 Township: 10.0S Range: 22.0E Meridian: S		9. API NUMBER: 43047519650000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 5/16/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex;"> <div style="flex: 1;"> <p>THE OPERATOR REQUESTS APPROVAL FOR A FIT WAIVER, A CLOSED LOOP DRILLING OPTION, AND A PRODUCTION CASING CHANGE. ALL OTHER ASPECTS OF THE PREVIOUSLY APPROVED DRILLING PLAN WILL NOT CHANGE. PLEASE SEE THE ATTACHMENT. THANK YOU.</p> </div> <div style="flex: 1; text-align: right; padding-right: 20px;"> <p style="color: red; font-weight: bold;">Approved by the Utah Division of Oil, Gas and Mining</p> <p style="color: red; font-weight: bold;">Date: May 24, 2012</p> <p style="color: red; font-weight: bold;">By: <u><i>Derek Duff</i></u></p> </div> </div>		
NAME (PLEASE PRINT) Cara Mahler		PHONE NUMBER 720 929-6029
SIGNATURE N/A		TITLE Regulatory Analyst I
DATE 5/16/2012		

Kerr-McGee Oil & Gas Onshore. L.P.**NBU 1022-12K1BS**

Surface: 2473 FNL / 2359 FWL SENW
BHL: 2567 FSL / 2142 FWL NESW

Section 12 T10S R22E

Uintah County, Utah

Mineral Lease: UT ST UO 01197-A ST

ONSHORE ORDER NO. 1**DRILLING PROGRAM**

1. & 2. **Estimated Tops of Important Geologic Markers:**
Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1,066'	
Birds Nest	1,358'	Water
Mahogany	1,722'	Water
Wasatch	4,102'	Gas
Mesaverde	6,275'	Gas
Sego	8,454'	Gas
TVD	8,454'	
TD	8,478'	

3. **Pressure Control Equipment** (Schematic Attached)

Please refer to the attached Drilling Program

4. **Proposed Casing & Cementing Program:**

Please refer to the attached Drilling Program

5. **Drilling Fluids Program:**

Please refer to the attached Drilling Program

6. **Evaluation Program:**

Please refer to the attached Drilling Program

7. Abnormal Conditions:

Maximum anticipated bottom hole pressure calculated at 8454' TVD, approximately equals
5,411 psi 0.64 psi/ft = actual bottomhole gradient

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,539 psi (bottom hole pressure
minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-

(0.22 psi/ft-partial evac gradient x TVD of next csg point))

8. Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

9. Variances:

Please refer to the attached Drilling Program.

Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- Blowout Prevention Equipment (BOPE) requirements;
- Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12 1/4 inch hole for the first 200 feet, then will drill a 11 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and

on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Variance for FIT Requirements

KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.


10. Other Information:

Please refer to the attached Drilling Program.



KERR-McGEE OIL & GAS ONSHORE LP
DRILLING PROGRAM

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP					DATE	May 16, 2012		
WELL NAME	NBU 1022-12K1BS					TD	8,454'	TVD	8,478' MD
FIELD	<u>Natural Buttes</u>		COUNTY	<u>Uintah</u>	STATE	<u>Utah</u>	FINISHED ELEVATION		5197.5
SURFACE LOCATION	SENW	2473 FNL	2359 FWL	Sec 12	T 10S	R 22E			
	Latitude:	39.963944	Longitude:	-109.388654		NAD 27			
BTM HOLE LOCATION	NESW	2567 FSL	2142 FWL	Sec 12	T 10S	R 22E			
	Latitude:	39.963279	Longitude:	-109.389434		NAD 27			
OBJECTIVE ZONE(S)	Wasatch/Mesaverde								
ADDITIONAL INFO	Regulatory Agencies: UDOGM (Minerals), UDOGM (Surface), UDOGM Tri-County Health Dept.								



RECEIVED: May. 16, 2012

NBU 1022-12K1BS

Drilling Program
6 of 7

KERR-McGEE OIL & GAS ONSHORE LP

DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS			
						LTC		DQX	
						BURST	COLLAPSE	TENSION	
CONDUCTOR	14"	0-40'				3,390	1,880	348,000	N/A
SURFACE	8-5/8"	0 to 2,170	28.00	IJ-55	LTC	2.49	1.85	6.54	N/A
						7,780	6,350	223,000	267,035
PRODUCTION	4-1/2"	0 to 5,000	11.60	I-80	DQX	1.11	1.16		3.36
						7,780	6,350	223,000	267,035
	4-1/2"	5,000 to 8,478'	11.60	I-80	LTC	1.11	1.16	6.83	

Surface Casing:

(Burst Assumptions: TD = 12.5 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
			+ 0.25 pps flocele				
Option 1	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
			+ 2% CaCl + 0.25 pps flocele				
SURFACE		NOTE: If well will circulate water to surface, option 2 will be utilized					
Option 2	LEAD	1,670'	65/35 Poz + 6% Gel + 10 pps gilsonite	160	35%	11.00	3.82
			+ 0.25 pps Flocele + 3% salt BWOW				
	TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
			+ 0.25 pps flocele				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION	LEAD	3,598'	Premium Lite II +0.25 pps	280	35%	12.00	3.38
			celloflake + 5 pps gilsonite + 10% gel				
			+ 0.5% extender				
	TAIL	4,880'	50/50 Poz/G + 10% salt + 2% gel	1,150	35%	14.30	1.31
			+ 0.1% R-3				

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well. 1 centralizer on the first 3 joints and one every third joint thereafter.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Nick Spence / Danny Showers / Chad Loesel


DATE:**DRILLING SUPERINTENDENT:**

Kenny Gathings / Lovel Young

DATE:

RECEIVED: May. 16, 2012

EXHIBIT A
NBU 1022-12K1BS



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK

Requested Drilling Options:

Kerr-McGee will use either a closed loop drilling system that will require one pit and one cuttings storage area to be constructed on the drilling pad or a traditional drilling operation with one pit used for drilling and completion operations. The cuttings storage area will be used to contain only the de-watered drill cuttings and will be lined and bermed to prevent any liquid runoff. The drill cuttings will be buried in the completion pit once completion operations are completed according to traditional pit closure standards. The pit will be constructed to allow for completion operations. The completion operations pit will be lined with a synthetic material 20 mil or thicker and will be used for the completing of the wells on the pad or used as part of our Aandarko Completions Transportation System (ACTS). Using the closed loop drilling system will allow Kerr-McGee to decrease the amount of disturbance/footprint on location compared to a single large drilling/completions pit.

If Kerr-McGee does not use a closed loop drilling system, it will construct a traditional drilling/completions pit to contain drill cuttings and for use in completion operations. The pit will be lined with a synthetic material 20 mil or thicker. The drill cuttings will be buried in the pit using traditional pit closure standards.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UT ST UO 01197-
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 1022-12K1BS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2473 FNL 2359 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 12 Township: 10.0S Range: 22.0E Meridian: S		9. API NUMBER: 43047519650000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 6/5/2012	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MIRU ROTARY RIG. FINISHED DRILLING FROM 2295' TO 8522' ON 6/4/2012. RAN 4-1/2" 11.6# I-80 PRODUCTION CASING. CEMENTED PRODUCTION CASING. RELEASED PIONEER 54 RIG ON 6/5/2012 @ 6:00 HRS. DETAILS OF CEMENT JOB WILL BE INCLUDED WITH THE WELL COMPLETION REPORT. WELL IS WAITING ON FINAL COMPLETION ACTIVITIES.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

FOR RECORD ONLY

June 06, 2012

NAME (PLEASE PRINT) Cara Mahler	PHONE NUMBER 720 929-6029	TITLE Regulatory Analyst I
SIGNATURE N/A	DATE 6/6/2012	

State of Utah - Notification Form

Operator Anadarko Petroleum Rig Name/# PIONEER 54
Submitted By STUART NEILSON Phone Number 435-790-2921
Well Name/Number NBU 1022-12K1BS
Qtr/Qtr SE4 NW4 Section 12 Township 10S Range 22E
Lease Serial Number UT ST UO 01997-A ST
API Number 4304751965

Casing – Time casing run starts, not cementing times.

- ☐ Production Casing
☐ Other

Date/Time _ _ AM ☐ PM ☐

BOPE

- ☒ Initial BOPE test at surface casing point
☐ Other

Date/Time 6/2/12 6 AM ☒ PM ☐

Rig Move

Location To:

Date/Time _____ AM ☐ PM ☐

Remarks _____

RECEIVED

JUN 01 2012

DIV. OF OIL, GAS & MINING

State of Utah - Notification Form

Operator Anadarko Petroleum Rig Name/# PIONEER 54
Submitted By STUART NEILSON Phone Number 435-790-2921
Well Name/Number NBU 1022-12K1BS
Qtr/Qtr SE4 NW4 Section 12 Township 10S Range 22E
Lease Serial Number UT ST UO 01997-A ST
API Number 4304751965

Casing – Time casing run starts, not cementing times.

☒ Production Casing
☐ Other

Date/Time 6/4/12 1600 AM ☐ PM ☒

BOPE

☐ Initial BOPE test at surface casing point
☐ Other

Date/Time _ _ AM ☐ PM ☐

Rig Move

Location To:

Date/Time _____ AM ☐ PM ☐

Remarks _____

RECEIVED


JUN 05 2012

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UT ST UO 01197-
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 1022-12K1BS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2473 FNL 2359 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 12 Township: 10.0S Range: 22.0E Meridian: S		9. API NUMBER: 43047519650000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 8/3/2012	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. No activity for the month of July 2012. Well TD at 8,522'.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY August 06, 2012		
NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBER 720 929-6304	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 8/3/2012	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UT ST UO 01197-
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 1022-12K1BS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2473 FNL 2359 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 12 Township: 10.0S Range: 22.0E Meridian: S		9. API NUMBER: 43047519650000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 7/26/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The operator is requesting approval to measure total gas produced from a pad, and to allocate gas production to the individual wells on the pad based upon multi-phase flow measurement at each well and periodic well tests. Please see the attached documents.		
Approved by the Utah Division of Oil, Gas and Mining Date: August 20, 2012 By: <u>Derek Duff</u>		
NAME (PLEASE PRINT) Cara Mahler		PHONE NUMBER 720 929-6029
SIGNATURE N/A		TITLE Regulatory Analyst I
DATE 7/26/2012		

The fluids from each well will be measured utilizing a multi-phase flow meter and then directed to a common separator for all wells on the pad. Liquids would be directed to tanks and the gas from all the wells measured through a calibrated orifice meter. The volume of gas measured through this meter, plus fuel gas consumed on location, will be the volume of gas that is produced from the pad. Gas volume for each individual well on the pad will be based on an allocation formula utilizing the total pad volume measured plus fuel gas consumed and the calculated volume from each well utilizing the multi-phase flow meters. The multi-phase flow meter volume calculation will be calibrated by periodic individual well tests.



Location Diagram with Multi-phase flow meters, main separator, test separator and associated storage tanks and flowlines.
28-Jun-12

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UT ST UO 01197-
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 1022-12K1BS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2473 FNL 2359 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 12 Township: 10.0S Range: 22.0E Meridian: S		9. API NUMBER: 43047519650000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 9/5/2012	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. No Activity for the month of August 2012. Well TD at 8,522.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY September 10, 2012		
NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBER 720 929-6304	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 9/5/2012	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UT ST UO 01197-
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 1022-12K1BS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2473 FNL 2359 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 12 Township: 10.0S Range: 22.0E Meridian: S		9. API NUMBER: 43047519650000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 10/3/2012	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. No Activity for the month of September 2012. Well TD at 8,522.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY October 04, 2012		
NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBER 720 929-6304	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 10/3/2012	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UT ST UO 01197-
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 1022-12K1BS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2473 FNL 2359 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 12 Township: 10.0S Range: 22.0E Meridian: S		9. API NUMBER: 43047519650000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 11/5/2012	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. No Activity for the month of October 2012. Well TD at 8,522.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY November 05, 2012		
NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBER 720 929-6304	TITLE Regularatory Analyst
SIGNATURE N/A	DATE 11/5/2012	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UT ST UO 01197-
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 1022-12K1BS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2473 FNL 2359 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 12 Township: 10.0S Range: 22.0E Meridian: S		9. API NUMBER: 43047519650000
PHONE NUMBER: 720 929-6511		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 12/4/2012	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Started completing the well. Well TD at 8,522.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY December 04, 2012		
NAME (PLEASE PRINT) Lindsey Frazier	PHONE NUMBER 720 929-6857	TITLE Regulatory Analyst II
SIGNATURE N/A	DATE 12/4/2012	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UT ST UO 01197-
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 1022-12K1BS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2473 FNL 2359 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 12 Township: 10.0S Range: 22.0E Meridian: S		9. API NUMBER: 43047519650000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 12/10/2012	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> CHANGE WELL NAME	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The subject well was placed on production on 12/10/2012. The Chronological Well History will be submitted with the well completion report.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY December 17, 2012		
NAME (PLEASE PRINT) Lindsey Frazier	PHONE NUMBER 720 929-6857	TITLE Regulatory Analyst II
SIGNATURE N/A	DATE 12/14/2012	

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8
(highlight changes)

5. LEASE DESIGNATION AND SERIAL NUMBER:
UT ST UO 01197-A ST

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT or CA AGREEMENT NAME
UTU63047A

8. WELL NAME and NUMBER:
NBU 1022-12K1BS

9. API NUMBER:
4304751965

10. FIELD AND POOL, OR WILDCAT
NATURAL BUTTES

11. QTR/QTR, SECTION, TOWNSHIP, RANGE,
MERIDIAN:
SENW 12 10S 22E S

12. COUNTY
UINTAH

13. STATE
UTAH

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☒ DRY ☐ OTHER

b. TYPE OF WORK: NEW WELL ☒ HORIZ. LATS. ☐ DEEP-EN ☐ RE-ENTRY ☐ DIFF. RESVR. ☐ OTHER

2. NAME OF OPERATOR:
KERR MCGEE OIL & GAS ONSHORE, L.P.

3. ADDRESS OF OPERATOR: P.O.BOX 173779 CITY DENVER STATE CO ZIP 80217
PHONE NUMBER: (720) 929-6000

4. LOCATION OF WELL (FOOTAGES)
AT SURFACE: SENW 2473FNL 2359FWL S12,T10S,R22E
AT TOP PRODUCING INTERVAL REPORTED BELOW: NESW 2567 FSL 2127 FWL S12,T10S,R22E
AT TOTAL DEPTH: NESW 2552 FSL 2147 FWL S12,T10S,R22E BHL by DOGM HSM

14. DATE SPUDDED: 4/6/2012
15. DATE T.D. REACHED: 6/4/2012
16. DATE COMPLETED: 12/10/2012
ABANDONED ☐ READY TO PRODUCE ☒

17. ELEVATIONS (DF, RKB, RT, GL):
5215 RKB

18. TOTAL DEPTH: MD 8,522
TVD 8,499
19. PLUG BACK T.D.: MD 8,465
TVD 8,442
20. IF MULTIPLE COMPLETIONS, HOW MANY? *

21. DEPTH BRIDGE MD
PLUG SET: TVD

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)

CBL/GR/CCL/TEMP

23.
WAS WELL CORED? NO ☒ YES ☐ (Submit analysis)
WAS DST RUN? NO ☒ YES ☐ (Submit report)
DIRECTIONAL SURVEY? NO ☐ YES ☒ (Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
20"	14" STL	36.7#	0	40		28			
11"	8 5/8" IJ-55	28#	0	2,280		975		0	
7 7/8"	4 1/2" I-80	11.6#	0	8,512		1,570		950	

RECEIVED
JAN 15 2013

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 3/8"	7,759							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) MESAVERDE	6,376	8,102			6,376 8,102	0.36	177	Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
6376-8102	PUMP 8204 BBLs SLICK H2O & 158,500 LBS 30/50 OTTAWA SAND
	8 STAGES

29. ENCLOSED ATTACHMENTS:

☐ ELECTRICAL/MECHANICAL LOGS
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION
☐ GEOLOGIC REPORT
☐ CORE ANALYSIS
☐ DST REPORT
☒ DIRECTIONAL SURVEY
☐ OTHER:

30. WELL STATUS:
PROD

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 12/10/2012	TEST DATE: 12/19/2012	HOURS TESTED: 24	TEST PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 2,507	WATER – BBL: 0	PROD. METHOD: FLOWING
CHOKE SIZE: 20/64	TBG. PRESS. 2,023	CSG. PRESS. 2,358	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS: PROD

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

SOLD

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				GREEN RIVER	1,141
				BIRD'S NEST	1,366
				MAHOGANY	1,830
				WASATCH	4,142
				MESAVERDE	6,286

35. ADDITIONAL REMARKS (Include plugging procedure)

The first 210' of the surface hole was drilled with a 12 1/4" bit. The remainder of surface hole was drilled with an 11" bit. DQX csg was run from surface to 5036'; LTC csg was run from 5036' to 8512'. Attached is the chronological well history, perforation report & final survey.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) LINDSEY FRAZIER

TITLE REGULATORY ANALYST

SIGNATURE

DATE 1/9/2013

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-12K1BS GREEN

Spud Date: 4/24/2012

Project: UTAH-UINTAH

Site: NBU 1022-12F4 PAD

Rig Name No: PIONEER 54/54, CAPSTAR 310/310

Event: DRILLING

Start Date: 4/10/2012

End Date: 6/5/2012

Active Datum: RKB @5,215.00usft (above Mean Sea Level)

UWI: SE/NW/0/10/S/22/E/12/0/0/26/PM/N/2473/W/0/2359/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
4/24/2012	16:30 - 18:00	1.50	DRLSUR	01	C	P		SKID TO LOCATION. RIG UP
	18:00 - 21:00	3.00	DRLSUR	01	B	P		WELD ON ROT HEAD, RIG UP BLOWIE LINE. PICK UP BHA, AIR OUT PUMPS
	21:00 - 23:00	2.00	DRLSUR	02	D	P		SPUD DRLG 12.25" SURFACE HOLE F/49' T/ 210' ROP=100' FPH WOB= 24-28K RPM= 55/105 SPP= 900/750 GPM= 620 TRQ= 2800/1700 PU/SO/RT= 32/25/28 HOLE CONDITION = GOOD
4/25/2012	23:00 - 0:00	1.00	DRLSUR	06	A	P		PULL OUT OF HOLE, LAY DOWN BIT
	0:00 - 1:30	1.50	DRLSUR	06	A	P		PU DIR TOOLS & SCRIBE /// TIH
	1:30 - 10:30	9.00	DRLSUR	02	D	P		DRLG 11" SURFACE HOLE F/ 210'- 1465' ROP= 1255' @ 139 FPH WOB= 24-28K RPM= 55/105 SPP= 1200/950 GPM= 595 TRQ=2800/1800 PU/SO/RT=100/75/82 LOST 50% RETURNS @ 1185' AIR ON @ 700 CFM
	10:30 - 11:00	0.50	DRLSUR	07	A	P		SERVICE RIG & EQUIPMENT
	11:00 - 18:00	7.00	DRLSUR	02	D	P		DRLG 11" SURFACE HOLE F/ 1465'-2295' ROP= 830' @ 119 FPH WOB= 24-28K RPM= 55/105 SPP= 1200/950 GPM= 595 TRQ=2800/2200 PU/SO/RT=122/72/99 LOST 75% RETURNS @ 1900' / BRING AIR UP TO 800 CFM
	18:00 - 18:30	0.50	DRLSUR	05	F	P		HOLE IN GOOD SHAPE /// POSITION= 8.92' HIGH & 3.83 RIGHT /// 95% ROTATE & 5% SLIDE
	18:30 - 22:00	3.50	DRLSUR	06	A	P		CIRC. & COND. HOLE FOR 8.625" CSG
	22:00 - 0:00	2.00	CSGSUR	12	C	P		LAY DOWN DRILL STRING & DIR TOOLS PJSM /// RUN 51 JT'S, 8.625", 28#, J-55, LT&C CSG /// SHOE SET @ 2270' /// BAFFLE @ 2223'
	0:00 - 0:30	0.50	CSGSUR	12	C	P		RUN 8.625" SURFACE CSG
4/26/2012	0:30 - 1:00	0.50	CSGSUR	05	F	P		CIRC 8.625" SURFACE CSG @ 2270'

US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-12K1BS GREEN

Spud Date: 4/24/2012

Project: UTAH-UINTAH

Site: NBU 1022-12F4 PAD

Rig Name No: PIONEER 54/54, CAPSTAR 310/310

Event: DRILLING

Start Date: 4/10/2012

End Date: 6/5/2012

Active Datum: RKB @5,215.00usft (above Mean Sea Level)

UWI: SE/NW/0/10/S/22/E/12/0/0/26/PM/N/2473/W/0/2359/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	1:00 - 2:30	1.50	CSGSUR	12	E	P		PJSM W/ PRO PETRO CMT CREW /// TEST LINES TO 1500 PSI /// PUMP 20 BBL'S WATER AHEAD FOLLOWED BY 20 BBL GEL WATER SPACER /// TAIL= 300 SX CLASS G CMT @ 15.8 WT & 1.15 YIELD /// DROP PLUG & DISPLACE W/ 138 BBL'S WATER /// PLUG DN @ 01:44 04/26/2012 /// BUMP PLUG W/ 550 PSI /// FINAL LIFT = 250 PSI /// CHECK FLOAT - HELD W/ .5 BBL'S BACK /// NO CIRC. & NO CMT TO SURFACE
	2:30 - 3:30	1.00	CSGSUR	14	A	P		RUN 200' OF 1" & TOP OUT W/ 150 SX CLASS G CMT @ 15.8 WT & 1.15 YIELD W/ 4% CaCL /// NO CMT TO SURFACE
	3:30 - 4:30	1.00	CSGSUR	12	E	P		CUT OFF CONDUCTOR & HANG 8.625" SURFACE CSG PUMP SECOND TOP OUT W/ 525 SX CLASS G CMT @ 15.8 WT & 1.15 YIELD W/ 4% CaCL /// CMT TO SURFACE
6/2/2012	0:00 - 0:30	0.50	DRLPRC	01	C	P		RELEASE RIG @ 04:30 04/26/2012 TO THE NBU 1022-12E4CS
	0:30 - 1:00	0.50	DRLPRC	14	A	P		SKID RIG 10' TO THE NBU 1022-12K1BS, CENTER & LEVEL RIG
	1:00 - 1:30	0.50	DRLPRC	14	A	P		NIPPLE UP BOPE
	1:30 - 6:00	4.50	DRLPRC	15	A	P		NIPPLE UP SWACO
	6:00 - 8:00	2.00	DRLPRC	15	A	P		TEST BOPE, RAMS & ALL VALVES 250 LOW, 5000 HIGH, ANN 2500, SURFACE CASING 1500 FOR 30 MIN'S
	8:00 - 9:00	1.00	DRLPRC	09	A	P		TEST SWACO TO 1000 PSI
	9:00 - 9:30	0.50	DRLPRC	14	B	P		CUT & SLIP DRILL LINE
	9:30 - 10:00	0.50	DRLPRC	14	B	P		CHANGE OUT SAVER SUB
	10:00 - 12:00	2.00	DRLPRC	06	A	P		INSTALL WEAR BUSHING, PRE-SPUD INSPECTION
	12:00 - 12:30	0.50	DRLPRC	02	E	P		P/U BIT, MOTOR, DIR TOOLS & SCRIBE, TRIP IN TO TOP OF CEMENT @ 2215'
	12:30 - 17:00	4.50	DRLPRC	02	D	P		DRILL CEMENT, BAFFEL @ 2241, SHOE @ 2289' & OPEN HOLE TO 2305'
								CLOSED LOOP SYSTEM
								DRILL F/ 2305 TO 3425', 1120' @ 248.8' PH
								WOB / 20-22
								RPM TOP DRIVE 50- 60, MOTOR-135
								SPM 200 GPM 586
								MW 8.5 VIS 26
								TRQ ON/OFF = 7/5 K
								PSI ON /OFF 2000-1600, DIFF 100-500
								PU/SO/RT = 115-100-90 K
								LOST 200 BBL'S TO FORMATION
								PUMPING SWEEPS WITH 5% LCM
								SLIDE = 78' IN .92
								ROT = 1119' IN 3.58 HRS312.6' PH
								NOV- ON LINE 2- DEWATERING
								3' ABOVE & 4.8' RIGHT OF THE LINE
								0 DRILL FLARE, 0 CONN FLARE
	17:00 - 17:30	0.50	DRLPRC	07	A	P		SERVICE RIG

US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-12K1BS GREEN

Spud Date: 4/24/2012

Project: UTAH-UINTAH

Site: NBU 1022-12F4 PAD

Rig Name No: PIONEER 54/54, CAPSTAR 310/310

Event: DRILLING

Start Date: 4/10/2012

End Date: 6/5/2012

Active Datum: RKB @5,215.00usft (above Mean Sea Level)

UWI: SE/NW/0/10/S/22/E/12/0/0/26/PM/N/2473/W/0/2359/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	17:30 - 0:00	6.50	DRLPRC	02	D	P		CLOSED LOOP SYSTEM DRILL F/ 3425 TO 4895', 1470' @ 226.1' PH WOB / 20-22 RPM TOP DRIVE 50- 60, MOTOR-135 SPM 200 GPM 586 MW 8.5 VIS 26 TRQ ON/OFF = 8-6 K PSI ON /OFF 2200-1900, DIFF 100-500 PU/SO/RT = 150-130-140 K LOST 200 BBLS TO FORMATION PUMPING SWEEPS WITH 5% LCM SLIDE = 44' IN .51 HRS = 86.3' PH ROT = 1426' IN 5.99 HRS = 238.1' PH NOV- ON LINE 2- DEWATERING 8.5 N & 14.6 W FROM TARGET CENTER 0 DRILL FLARE, 0 CONN FLARE
6/3/2012	0:00 - 6:00	6.00	DRLPRC	02	D	P		CLOSED LOOP SYSTEM DRILL F/ 4895' TO 6080', 1185' @ 197.5' PH WOB / 20-22 RPM TOP DRIVE 50- 60, MOTOR-135 SPM 200 GPM 586 MW 8.5 VIS 26 TRQ ON/OFF = 8-6 K PSI ON /OFF 2200-1900, DIFF 100-500 PU/SO/RT = 160-140-150 K LOST 200 BBLS TO FORMATION PUMPING SWEEPS WITH 5% LCM SLIDE = 29' IN .42 HRS = 69' PH ROT = 1156' IN 5.58 HRS = 207.1' PH NOV- ON LINE 2- DEWATERING 12' N & 7' W FROM TARGET CENTER 0 DRILL FLARE, 0 CONN FLARE CHANGE SWAB IN PUMP
	6:00 - 6:30	0.50	DRLPRC	08	B	P		CLOSED LOOP SYSTEM
	6:30 - 17:00	10.50	DRLPRC	02	D	P		DRILL F/ 6080' TO 7502', 1422' @ 135.4' PH WOB / 20-22 RPM TOP DRIVE 50- 60, MOTOR-135 SPM 200 GPM 586 MW 8.5 VIS 26 TRQ ON/OFF = 9-8 K PSI ON /OFF 2200-1900, DIFF 100-500 PU/SO/RT = 195-135-155 K LOST 300 BBLS TO FORMATION PUMPING SWEEPS WITH 5% LCM SLIDE = 77' IN 1.58 HRS = 48.7' PH ROT = 1345' IN 8.92 HRS = 150.8' PH NOV- ON LINE 2- DEWATERING 9.9' N & 5.5' W FROM TARGET CENTER 0 DRILL FLARE, 0 CONN FLARE GAS @ 7300'
	17:00 - 17:30	0.50	DRLPRC	07	A	P		SERVICE RIG, F/T ANN & HCR VALVE

US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-12K1BS GREEN

Spud Date: 4/24/2012

Project: UTAH-UINTAH

Site: NBU 1022-12F4 PAD

Rig Name No: PIONEER 54/54, CAPSTAR 310/310

Event: DRILLING

Start Date: 4/10/2012

End Date: 6/5/2012

Active Datum: RKB @5,215.00usft (above Mean Sea Level)

UWI: SE/NW/0/10/S/22/E/12/0/0/26/PM/N/2473/W/0/2359/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	17:30 - 0:00	6.50	DRLPRC	02	D	P		CLOSED LOOP SYSTEM DRILL F/ 7502 TO 8340', 838' @ 128.9' PH WOB / 20-22 RPM TOP DRIVE 50- 60, MOTOR-135 SPM 200 GPM 586 MW 8.5 VIS 26 TRQ ON/OFF = 10-8 K PSI ON /OFF 2300-2000, DIFF 100-500 PU/SO/RT = 200-150-175 K LOST 200 BBLS TO FORMATION PUMPING SWEEPS WITH 5% LCM SLIDE = 20' IN .58 HRS = 34.5' PH ROT = 818' IN 5.92 HRS = 138.2' PH NOV- ON LINE 2- DEWATERING 8' S & 7' E FROM TARGET CENTER 10' DRILL FLARE, 10 CONN FLARE GAS @ 7300'
6/4/2012	0:00 - 1:30	1.50	DRLPRC	02	D	P		CLOSED LOOP SYSTEM DRILL F/ 8340 TO 8522', 18182' @ 121.3' PH WOB / 20-22 RPM TOP DRIVE 50- 60, MOTOR-135 SPM 200 GPM 586 MW 8.5 VIS 26 TRQ ON/OFF = 10-8 K PSI ON /OFF 2300-2000, DIFF 100-500 PU/SO/RT = 200-150-175 K LOST 50 BBLS TO FORMATION PUMPING SWEEPS WITH 5% LCM SLIDE = 0 ROT = 100% NOV- ON LINE 2- DEWATERING 8' S & 7' E FROM TARGET CENTER 10' DRILL FLARE, 10 CONN FLARE GAS @ 7300'
	1:30 - 2:30	1.00	DRLPRC	05	G	P		DISPLACE HOLE WITH 11.2 PPG, 45 VIS MUD
	2:30 - 4:30	2.00	DRLPRC	05	C	P		CIRC & COND HOLE FOR SHORT TRIP
	4:30 - 9:30	5.00	DRLPRC	06	E	P		SHORT TRIP TO SURFACE CASING SHOE & BACK TO BOTTOM
	9:30 - 11:00	1.50	DRLPRC	05	C	P		CIRC & COND HOLE FOR TRIP OUT
	11:00 - 14:00	3.00	DRLPRC	06	D	P		TRIP OUT TO RUN PROD CASING
	14:00 - 14:30	0.50	DRLPRC	14	B	P		PULL WEAR BUSHING
	14:30 - 22:30	8.00	DRLPRC	12	C	P		HELD SAFETY MEETING, R/U & RUN 80 JTS I-80 LTC, 112 JTS I-80 P-110, LAND CASING, R/D CASING CREW, SHOE @ 8511, FLOAT @ 8466'
	22:30 - 0:00	1.50	DRLPRC	05	D	P		CIRC OUT GAS TO CEMENT
6/5/2012	0:00 - 3:00	3.00	DRLPRC	12	E	P		HELD SAFETY MEETING, PSI TEST LINES TO 4500, PUMP 25 BBLS WATER SPACER, LEAD 420 SACKS 12 PPG 2.26 YLD, TAIL 1150 SACKS 14.3 PPG 1.32 YLD, DROP PLUG & DISPLACE WITH 132 BBLS CLAYCARE WATER, CHECK FLOATS, FLOATS HELD, FULL RETURNS THOUGH OUT JOB WITH 30 BBLS CEMENT TO CATCH TANK, 1.5 BACK TO TRUCK, BUMP PLUG WITH 3109 PSI (596 PSI OVER FINAL LIFT OF 2513), EST TOP OF TAIL 3600', PLUG BACK TO 8466'

US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-12K1BS GREEN				Spud Date: 4/24/2012						
Project: UTAH-UINTAH			Site: NBU 1022-12F4 PAD				Rig Name No: PIONEER 54/54, CAPSTAR 310/310			
Event: DRILLING			Start Date: 4/10/2012					End Date: 6/5/2012		
Active Datum: RKB @5,215.00usft (above Mean Sea Level)				UWI: SE/NW/0/10/S/22/E/12/0/0/26/PM/N/2473/W/0/2359/0/0						
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation		
	3:00 - 3:30	0.50	DRLPRC	14	B	P		SET PACK OFF		
	3:30 - 4:00	0.50	DRLPRC	14	A	P		N/D BOPE		
	4:00 - 4:30	0.50	DRLPRC	14	A	P		N/D SWACO		
	4:30 - 6:00	1.50	DRLPRC	01	E	P		PREPARE TO SKID TO THE NBU 1022-12E4CS, RELEASE RIG @ 06:00 6/5/12		

1 General

1.1 Customer Information

Company	US ROCKIES REGION
Representative	
Address	

1.2 Well/Wellbore Information

Well	NBU 1022-12K1BS GREEN	Wellbore No.	OH
Well Name	NBU 1022-12K1BS	Wellbore Name	NBU 1022-12K1BS
Report No.	1	Report Date	11/5/2012
Project	UTAH-UINTAH	Site	NBU 1022-12F4 PAD
Rig Name/No.		Event	COMPLETION
Start Date	11/5/2012	End Date	12/10/2012
Spud Date	4/24/2012	Active Datum	RKB @5,215.00usft (above Mean Sea Level)
UWI	SE/NW/0/10/S/22/E/12/0/0/26/PM/N/2473/W/0/2359/0/0		

1.3 General

Contractor		Job Method		Supervisor	
Perforated Assembly		Conveyed Method			

1.4 Initial Conditions

Fluid Type		Fluid Density	
Surface Press		Estimate Res Press	
TVD Fluid Top		Fluid Head	
Hydrostatic Press		Press Difference	
Balance Cond	NEUTRAL		

1.5 Summary

Gross Interval	6,376.0 (usft)-8,102.0 (usft)	Start Date/Time	11/5/2012 12:00AM
No. of Intervals	51	End Date/Time	11/5/2012 12:00AM
Total Shots	177	Net Perforation Interval	59.00 (usft)
Avg Shot Density	3.00 (shot/ft)	Final Surface Pressure	
		Final Press Date	

2 Intervals

2.1 Perforated Interval

Date	Formation/ Reservoir	CCL@ (usft)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diamete r (in)	Carr Type /Stage No	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
11/5/2012 12:00AM	MESAVERDE/			6,376.0	6,377.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	

2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr Type /Stage No	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
11/5/2012 12:00AM	MESAVERDE/			6,400.0	6,401.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,446.0	6,447.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,514.0	6,515.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,522.0	6,523.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,540.0	6,541.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,547.0	6,548.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,595.0	6,596.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,612.0	6,613.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,623.0	6,624.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,675.0	6,676.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,704.0	6,705.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,744.0	6,745.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,776.0	6,777.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,784.0	6,785.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,862.0	6,863.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,886.0	6,887.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,907.0	6,908.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,919.0	6,920.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			6,976.0	6,977.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,072.0	7,073.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,079.0	7,080.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	

2.1 Perforated Interval (Continued)


Date	Formation/ Reservoir	CCL@ (usft)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr Type /Stage No	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
11/5/2012 12:00AM	MESAVERDE/			7,101.0	7,102.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,230.0	7,231.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,239.0	7,240.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,283.0	7,284.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,298.0	7,299.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,334.0	7,337.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,417.0	7,418.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,431.0	7,432.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,485.0	7,486.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,535.0	7,536.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,585.0	7,586.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,592.0	7,594.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,638.0	7,639.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,668.0	7,669.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,687.0	7,688.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,702.0	7,704.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,738.0	7,740.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,782.0	7,783.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,796.0	7,797.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,812.0	7,813.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,820.0	7,821.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	

2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diamete r (in)	Carr Type /Stage No	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
11/5/2012 12:00AM	MESAVERDE/			7,865.0	7,866.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,876.0	7,877.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,916.0	7,918.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			7,958.0	7,959.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			8,014.0	8,015.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			8,020.0	8,021.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			8,068.0	8,070.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
11/5/2012 12:00AM	MESAVERDE/			8,100.0	8,102.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	

3 Plots

3.1 Wellbore Schematic



US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-12K1BS GREEN

Spud Date: 4/24/2012

Project: UTAH-UINTAH

Site: NBU 1022-12F4 PAD

Rig Name No: GWS 1/1

Event: COMPLETION

Start Date: 11/5/2012

End Date: 12/10/2012

Active Datum: RKB @5,215.00usft (above Mean Sea Level)

UWI: SE/NW/0/10/S/22/E/12/0/0/26/PM/N/2473/W/0/2359/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
4/24/2012	-							
4/25/2012	-							
11/5/2012	12:00 - 13:30	1.50	FRAC	33	C	P		FILL SURFACE CSG. MIRU B&C QUICK TEST. PSI TEST T/ 1000 PSI. HELD FOR 15 MIN LOST 15 PSI. PSI TEST T/ 3500 PSI. HELD FOR 15 MIN LOST 41 PSI. 1ST PSI TEST T/ 7000 PSI. HELD FOR 30 MIN LOST 82 PSI. NO COMMUNICATION OR MIGRATION WITH SURFACE CSG BLEED OFF PSI. MOVE T/ NEXT WELL. SWFW
11/8/2012	7:00 - 15:00	8.00	FRAC	37		P		PERF STG 1)PU 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH PERF AS PER PERF DESIGN. POOH. SWFW
11/12/2012	6:45 - 7:00	0.25	FRAC	48		P		HSM. HIGH PSI LINES, AND WIRE LINE AWAIRNESS.

US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-12K1BS GREEN

Spud Date: 4/24/2012

Project: UTAH-UINTAH

Site: NBU 1022-12F4 PAD

Rig Name No: GWS 1/1

Event: COMPLETION

Start Date: 11/5/2012

End Date: 12/10/2012

Active Datum: RKB @5,215.00usft (above Mean Sea Level)

UWI: SE/NW/0/10/S/22/E/12/0/0/26/PM/N/2473/W/0/2359/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	7:00 - 18:00	11.00	FRAC	36	B	P		<p>PSI TEST LINES T/ 8000 PSI. LOST 70 PSI. BLEED OFF PSI.</p> <p>FRAC STG 1)WHP 1120 PSI, BRK 3252 PSI@4.7 BPM. ISIP 2550 PSI, FG. 0.75 CALC PERFS OPEN @ 48.5 BPM @ 5400PSI = 86% ISIP 2540 PSI, FG. 0.75, NPI -10 PSI. MP 6745 PSI, MR 49.6 BPM, AP 5099 PSI, AR 40.1 BPM, PUMPED 30/50 OWATTA SAND. SWI, XO T/ WL.</p> <p>PERF STG 2)PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 7948' P/U PERF AS PER DESIGN. POOH, XO T/ FRAC.</p> <p>FRAC STG 2)WHP 2187 PSI, BRK 2785 PSI@4.7 BPM. ISIP 2345 PSI, FG. 0.73 CALC PERFS OPEN @ 50.4 BPM @ 4300PSI = 100% ISIP 2460 PSI, FG. 0.75, NPI 115 PSI. MP 5489 PSI, MR 50.6 BPM, AP 4228 PSI, AR 49.8 BPM, PUMPED 30/50 OWATTA SAND. SWI, XO T/ WL.</p> <p>PERF STG 3)PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 7770' P/U PERF AS PER DESIGN. POOH, XO T/ FRAC.</p> <p>FRAC STG 3)WHP 802 PSI, BRK 3409 PSI@4.7 BPM. ISIP 2595 PSI, FG. 0.77 CALC PERFS OPEN @ 50.1 BPM @ 4632PSI = 100% ISIP 2683 PSI, FG. 0.78, NPI 88 PSI. MP 4856 PSI, MR 50.2 BPM, AP 4419 PSI, AR 50.1 BPM, PUMPED 30/50 OWATTA SAND. SWI, XO T/ WL.</p> <p>PERF STG 4)PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 7624' P/U PERF AS PER DESIGN. POOH, XO T/ FRAC.</p> <p>FRAC STG 4)WHP 1950 PSI, BRK 3059 PSI@4.7 BPM. ISIP 2091 PSI, FG. 0.71 CALC PERFS OPEN @ 49.8 BPM @ 4380PSI = 100% ISIP 2129 PSI, FG. 0.72, NPI 38 PSI. MP 4574 PSI, MR 50 BPM, AP 4059 PSI, AR 49.3 BPM, PUMPED 30/50 OWATTA SAND. SWIFN.</p>

US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-12K1BS GREEN

Spud Date: 4/24/2012

Project: UTAH-UINTAH

Site: NBU 1022-12F4 PAD

Rig Name No: GWS 1/1

Event: COMPLETION

Start Date: 11/5/2012

End Date: 12/10/2012

Active Datum: RKB @5,215.00usft (above Mean Sea Level)

UWI: SE/NW/0/10/S/22/E/12/0/0/26/PM/N/2473/W/0/2359/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
11/13/2012	8:35 - 18:00	9.42	FRAC	36	B	P		<p>PERF STG 5)PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 7367' P/U PERF AS PER DESIGN. POOH, XO T/ WL</p> <p>FRAC STG 5)WHP 1694 PSI, BRK 2128 PSI@4.7 BPM. ISIP 1758 PSI, FG. 0.67 CALC PERFS OPEN @ 55.6 BPM @ 4076PSI = 100% ISIP 2160 PSI, FG. 0.73, NPI 402 PSI. MP 4098 PSI, MR 55.6 BPM, AP 3893 PSI, AR 55.2 BPM, PUMPED 30/50 OWATTA SAND. SWI, XO T/ WL.</p> <p>PERF STG 6)PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 7132' P/U PERF AS PER DESIGN. POOH. XO T/ FRAC.</p> <p>FRAC STG 6)WHP 771 PSI, BRK 2629 PSI@4.7 BPM. ISIP 1760 PSI, FG. 0.69 CALC PERFS OPEN @ 55.7 BPM @ 3900PSI = 100% ISIP 2233 PSI, FG. 0.75, NPI 473 PSI. MP 4210 PSI, MR 55.7 BPM, AP 3883 PSI, AR 55.6 BPM, PUMPED 30/50 OWATTA SAND. SWI, XO T/ WL.</p> <p>PERF STG 7)PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 6815' P/U PERF AS PER DESIGN. POOH, XO T/ FRAC.</p> <p>FRAC STG 7)WHP 712 PSI, BRK 1751 PSI@4.7 BPM. ISIP 1303 PSI, FG. 0.63 CALC PERFS OPEN @ 55.4 BPM @ 3785 PSI = 100% ISIP 2052 PSI, FG. 0.74, NPI 749 PSI. MP 4053 PSI, MR 55.4 BPM, AP 3757 PSI, AR 55.2 BPM, PUMPED 30/50 OWATTA SAND. SWIFN.</p>
11/14/2012	8:00 - 15:00	7.00	FRAC	36	B	P		<p>PERF STG 8)PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 6578' P/U PERF AS PER DESIGN. POOH, XO T/ FRAC.</p> <p>FRAC STG 8)WHP 183 PSI, BRK 2129 PSI @ 4.7 BPM. ISIP 1369 PSI, FG .0.64, CALC PERFS OPEN @ 55.4 BPM @ 4198 PSI = 100% HOLES OPEN. ISIP 2187 PSI, FG .0.77, NPI 818 PSI. MP 4216 PSI, MR 55.4 BPM, AP 3945 PSI, AR 55.2 BPM, PUMPED 30/50 OWATTA SAND. SWI, XO T/ WL.</p> <p>PU 4 1/2 8K HAL CBP. RIH SET KILL PLUG @ 6326'. POOH, SWI, DONE FRACING THIS WELL.</p> <p>TOTAL SAND = 158,500 LBS TOTAL CLFL = 8204 BBLs</p>

US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-12K1BS GREEN

Spud Date: 4/24/2012

Project: UTAH-UINTAH

Site: NBU 1022-12F4 PAD

Rig Name No: GWS 1/1

Event: COMPLETION

Start Date: 11/5/2012

End Date: 12/10/2012

Active Datum: RKB @5,215.00usft (above Mean Sea Level)

UWI: SE/NW/0/10/S/22/E/12/0/0/26/PM/N/2473/W/0/2359/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
12/7/2012	10:00 - 17:00	7.00	DRLOUT	31	I	P		3 OF 6, MIRU, SPOT EQUIP, ND WH, NU 10K BOP, RU FLOOR & TBG EQUIP, SPOT TBG TRAILER & INSTAL HAND RAILS, PU 3 7/8" BIT, POBS, TALLY & PU TBG, RU P/S, FILL TBG & BREAK CIRC, P/T BOP TO 3,000 PSI, TEST GOOD, READY TO D/O PLUGS ON MONDAY, DRAIN & WINTERIZE EQUIP, SWI, SDFWE.
12/10/2012	7:00 - 7:15	0.25	DRLOUT	48		P		HSM, SLIPS, TRIPS & FALLS, D/O PLUGS, LANDING TBG

US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-12K1BS GREEN

Spud Date: 4/24/2012

Project: UTAH-UINTAH

Site: NBU 1022-12F4 PAD

Rig Name No: GWS 1/1

Event: COMPLETION

Start Date: 11/5/2012

End Date: 12/10/2012

Active Datum: RKB @5,215.00usft (above Mean Sea Level)

UWI: SE/NW/0/10/S/22/E/12/0/0/26/PM/N/2473/W/0/2359/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	7:15 - 15:00	7.75	DRLOUT	44	C	P		<p>3 OF 6, SURFACE CSG VALVE OPEN & LOCKED, BREAK CIRC, D/O PLUGS.</p> <p>C/O 15' SAND, TAG 1ST PLUG @ 6,326' DRL PLUG IN 11 MIN. 200 PSI INCREASE RIH, CSG PRESS 0 PSI. ((WELL FLOWING ON IT'S OWN))</p> <p>C/O 20' SAND, TAG 2ND PLUG @ 6,578' DRL PLUG IN 10 MIN. 100 PSI INCREASE RIH, CSG PRESS 600 PSI.</p> <p>C/O 30' SAND, TAG 3RD PLUG @ 6,815' DRL PLUG IN 9 MIN. 500 PSI INCREASE RIH, CSG PRESS 300 PSI.</p> <p>C/O 25' SAND, TAG 4TH PLUG @ 7,132' DRL PLUG IN 8 MIN. 300 PSI INCREASE RIH, CSG PRESS 400 PSI.</p> <p>C/O 20' SAND, TAG 5TH PLUG @ 7,367' DRL PLUG IN 8 MIN. 200 PSI INCREASE RIH, CSG PRESS 600 PSI.</p> <p>C/O 25' SAND, TAG 6TH PLUG @ 7,624' DRL PLUG IN 9 MIN. 300 PSI INCREASE RIH, CSG PRESS 600 PSI.</p> <p>C/O 25' SAND, TAG 7TH PLUG @ 7,770' DRL PLUG IN 9 MIN. 400 PSI INCREASE RIH, CSG PRESS 500 PSI.</p> <p>C/O 20' SAND, TAG 8TH PLUG @ 7,948' DRL PLUG IN 8 MIN. 500 PSI INCREASE RIH, CSG PRESS 600 PSI.</p> <p>PBTD @ 8,465', BTM PERF @ 8,102', RIH TAGGED @ 8,375', 273' PAST BTM PERF W/ 264 JTS 2 3/8" L-80 TBG, LD 20 JTS, PU & STRIP IN TBG HANGER & LAND TBG W/ 244 JTS 2 3/8" L-80, EOT 7,759.40'.</p> <p>RD POWER SWIVEL, FLOOR & TBG EQUIP, ND BOPS, NU WH, DROP BALL TO SHEAR OFF BIT 2,700 PSI, LET BIT FALL FOR 20 MIN. P/T FLOW LINE FROM WH TO HAL 9000 TO 3,000 PSI W/ RIG PUMP, NO VISIBLE LEAKS.</p> <p>NOTE: PUMPED 64 BBLs TMAC & SCALE INHIB DOWN CSG TO TOP PERF @ 6,376'. MIXTURE 120 BBLs TMAC & 5 GALLON SCALE INHIB.</p> <p>TURN OVER TO FLOW BACK CREW & SALES, RD & MOVE TO NEXT WELL ON PAD, DRAIN & WINTERIZE EQUIP, SDFN.</p> <p>KB= 19' 4 1/16" CAMERON HANGER= .83' TBG</p>




US ROCKIES REGION
Operation Summary Report

Well: NBU 1022-12K1BS GREEN				Spud Date: 4/24/2012						
Project: UTAH-UINTAH			Site: NBU 1022-12F4 PAD				Rig Name No: GWS 1/1			
Event: COMPLETION			Start Date: 11/5/2012					End Date: 12/10/2012		
Active Datum: RKB @5,215.00usft (above Mean Sea Level)				UWI: SE/NW/0/10/S/22/E/12/0/0/26/PM/N/2473/W/0/2359/0/0						
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation		
								DELIVERED 283 JTS 244 JTS 2 3/8" L-80 = 7,737.37' TBG USED 244 JTS POBS= 2.20' TBG RETURNED 39 JTS EOT @ 7,759.40' ((2 W/ BAD THREADS))		
	15:00 - 15:00	0.00	DRLOUT	50				TWTR= 8,204 BBLS TWR= 3,500 BBLS TWLTR= 4,704 BBLS WELL TURNED TO SALES @ 1440 HR ON 12/10/2012 1300 MCFD, FCP 2200#, FTP 2195#, 20/64" CK.		
12/11/2012	-									
12/20/2012	7:00 -			50				WELL IP'D ON 12/20/2012 - 2507 MCFD, 0 BOPD, 0 BWPD, CP 2358#, FTP 2022#, CK 20/64, LP 299#, 24 HRS		

WELL DETAILS: NBU 1022-12K1BS

GL 5198 & KB 19 @ 5217.00ft (PIONEER 54)

+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	14516993.85	2091935.29	39.963944	-109.388654



PROJECT DETAILS: UTAH - UTM (feet), NAD27, Zone 12N
 Geodetic System: Universal Transverse Mercator (US Survey Feet)
 Datum: NAD 1927 (NADCON CONUS)
 Ellipsoid: Clarke 1866
 Zone: Zone 12N (114 W to 108 W)
 Location: SECTION 12 T10S R22E
 System Datum: Mean Sea Level

Design: OH (NBU 1022-12K1BS/OH)

Created By: Gabe Kendall Date: 9:40 June 29 2012



Scientific Drilling

US ROCKIES REGION PLANNING

UTAH - UTM (feet), NAD27, Zone 12N

NBU 1022-12F4 PAD

NBU 1022-12K1BS

OH

Design: OH

Standard Survey Report

29 June, 2012

Company:	US ROCKIES REGION PLANNING	Local Co-ordinate Reference:	Well NBU 1022-12K1BS
Project:	UTAH - UTM (feet), NAD27, Zone 12N	TVD Reference:	GL 5198 & KB 19 @ 5217.00ft (PIONEER 54)
Site:	NBU 1022-12F4 PAD	MD Reference:	GL 5198 & KB 19 @ 5217.00ft (PIONEER 54)
Well:	NBU 1022-12K1BS	North Reference:	True
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM 5000.1 Single User Db

Project	UTAH - UTM (feet), NAD27, Zone 12N		
Map System:	Universal Transverse Mercator (US Survey Feet)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Zone 12N (114 W to 108 W)		

Site		NBU 1022-12F4 PAD, SECTION 12 T10S R22E			
Site Position:		Northing:	14,516,999.17 usft	Latitude:	39.963959
From:	Lat/Long	Easting:	2,091,927.06 usft	Longitude:	-109.388683
Position Uncertainty:	0.00 ft	Slot Radius:	13.200 in	Grid Convergence:	1.04 °

Well	NBU 1022-12K1BS, 2473 FNL 2359 FWL					
Well Position	+N/-S	0.00 ft	Northing:	14,516,993.85 usft	Latitude:	39.963944
	+E/-W	0.00 ft	Easting:	2,091,935.28 usft	Longitude:	-109.388654
Position Uncertainty		0.00 ft	Wellhead Elevation:	ft	Ground Level:	5,198.00 ft

Wellbore	OH				
Magnetics	Model Name	Sample Date	Declination	Dip Angle	Field Strength
			(°)	(°)	(nT)
	IGRF2010	2011/08/26	11.00	65.85	52,303

Design	OH				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction	
	(ft)	(ft)	(ft)	(°)	
	0.00	0.00	0.00	226.26	

Survey Program	Date 2012/06/29			
From	To	Survey (Wellbore)	Tool Name	Description
(ft)	(ft)			
10.00	2,249.00	Survey #1 SDI MWD SURFACE (OH)	SDI MWD	SDI MWD - Standard ver 1.0.1
2,325.00	8,522.00	Survey #2 SDI MWD PRODUCTION (OH)	SDI MWD	SDI MWD - Standard ver 1.0.1

Survey										
Measured	Inclination	Azimuth	Vertical	+N/-S	+E/-W	Vertical	Dogleg	Build	Turn	
Depth	(°)	(°)	Depth	(ft)	(ft)	Section	Rate	Rate	Rate	
(ft)			(ft)			(ft)	(°/100ft)	(°/100ft)	(°/100ft)	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
10.00	0.00	0.00	10.00	0.00	0.00	0.00	0.00	0.00	0.00	
238.00	0.00	249.89	238.00	0.00	0.00	0.00	0.00	0.00	0.00	
FIRST SDI MWD SURFACE SURVEY										
329.00	1.14	226.86	328.99	-0.62	-0.66	0.91	1.25	1.25	0.00	
420.00	2.64	228.62	419.94	-2.62	-2.89	3.90	1.65	1.65	1.93	
514.00	5.19	228.44	513.71	-6.88	-7.70	10.32	2.71	2.71	-0.19	
608.00	6.33	229.15	607.24	-13.09	-14.80	19.74	1.22	1.21	0.76	
703.00	7.56	227.65	701.54	-20.72	-23.38	31.22	1.31	1.29	-1.58	
797.00	8.88	226.33	794.57	-29.90	-33.20	44.66	1.42	1.40	-1.40	

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N
Site: NBU 1022-12F4 PAD
Well: NBU 1022-12K1BS
Wellbore: OH
Design: OH

Local Co-ordinate Reference: Well NBU 1022-12K1BS
TVD Reference: GL 5198 & KB 19 @ 5217.00ft (PIONEER 54)
MD Reference: GL 5198 & KB 19 @ 5217.00ft (PIONEER 54)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
892.00	9.23	223.17	888.39	-40.52	-43.72	59.60	0.64	0.37	-3.33
986.00	8.88	231.70	981.22	-50.51	-54.57	74.35	1.47	-0.37	9.07
1,080.00	8.94	233.06	1,074.09	-59.40	-66.10	88.82	0.23	0.06	1.45
1,176.00	9.50	230.64	1,168.85	-68.91	-78.19	104.13	0.71	0.58	-2.52
1,271.00	9.85	224.75	1,262.50	-79.65	-89.97	120.07	1.10	0.37	-6.20
1,366.00	8.88	220.80	1,356.23	-90.97	-100.48	135.49	1.22	-1.02	-4.16
1,460.00	8.21	218.32	1,449.19	-101.73	-109.38	149.36	0.81	-0.71	-2.64
1,553.00	7.83	223.52	1,541.28	-111.53	-117.86	162.27	0.88	-0.41	5.59
1,646.00	8.64	223.98	1,633.32	-121.15	-127.08	175.57	0.87	0.87	0.49
1,739.00	8.00	224.93	1,725.34	-130.76	-136.50	189.02	0.70	-0.69	1.02
1,833.00	8.30	225.83	1,818.39	-140.12	-145.98	202.35	0.35	0.32	0.96
1,929.00	8.56	226.78	1,913.35	-149.84	-156.16	216.42	0.31	0.27	0.99
2,025.00	8.53	228.80	2,008.29	-159.42	-166.72	230.68	0.31	-0.03	2.10
2,117.00	7.74	224.49	2,099.36	-168.34	-176.20	243.69	1.08	-0.86	-4.68
2,249.00	8.27	226.56	2,230.08	-181.20	-189.32	262.07	0.46	0.40	1.57
LAST SDI MWD SURFACE SURVEY									
2,325.00	7.83	223.33	2,305.33	-188.73	-196.84	272.70	0.83	-0.58	-4.25
FIRST SDI MWD PRODUCTION SURVEY									
2,419.00	6.68	228.95	2,398.57	-196.98	-205.36	284.56	1.44	-1.22	5.98
2,514.00	5.63	229.04	2,493.03	-203.66	-213.05	294.73	1.11	-1.11	0.09
2,609.00	4.92	235.19	2,587.62	-209.04	-219.91	303.41	0.95	-0.75	6.47
2,704.00	3.78	245.56	2,682.35	-212.66	-226.11	310.39	1.45	-1.20	10.92
2,798.00	2.73	246.62	2,776.20	-214.83	-230.98	315.41	1.12	-1.12	1.13
2,893.00	1.58	245.21	2,871.13	-216.28	-234.25	318.77	1.21	-1.21	-1.48
2,988.00	1.67	219.99	2,966.09	-217.89	-236.33	321.39	0.75	0.09	-26.55
3,083.00	0.35	171.91	3,061.08	-219.24	-237.18	322.93	1.54	-1.39	-50.61
3,178.00	0.44	176.92	3,156.07	-219.89	-237.12	323.34	0.10	0.09	5.27
3,272.00	0.53	210.06	3,250.07	-220.63	-237.31	323.99	0.31	0.10	35.26
3,367.00	1.32	186.50	3,345.06	-222.09	-237.66	325.26	0.91	0.83	-24.80
3,462.00	0.97	127.97	3,440.04	-223.68	-237.15	325.98	1.22	-0.37	-61.61
3,557.00	1.03	152.62	3,535.03	-224.93	-236.12	326.11	0.45	0.06	25.95
3,651.00	0.88	152.75	3,629.01	-226.32	-235.40	326.55	0.16	-0.16	0.14
3,746.00	1.14	168.84	3,724.00	-227.90	-234.89	327.27	0.40	0.27	16.94
3,841.00	1.32	172.53	3,818.98	-229.91	-234.56	328.42	0.21	0.19	3.88
3,936.00	0.44	136.14	3,913.97	-231.26	-234.17	329.07	1.05	-0.93	-38.31
4,031.00	0.67	132.58	4,008.96	-231.90	-233.50	329.03	0.24	0.24	-3.75
4,125.00	0.88	142.12	4,102.95	-232.84	-232.66	329.07	0.26	0.22	10.15
4,220.00	1.14	148.27	4,197.94	-234.22	-231.71	329.34	0.30	0.27	6.47
4,315.00	1.14	151.96	4,292.92	-235.85	-230.77	329.79	0.08	0.00	3.88
4,410.00	0.09	338.03	4,387.91	-236.62	-230.35	330.02	1.29	-1.11	-183.08
4,505.00	0.35	176.40	4,482.91	-236.84	-230.36	330.18	0.46	0.27	-170.14
4,600.00	0.44	155.56	4,577.91	-237.46	-230.19	330.49	0.18	0.09	-21.94
4,695.00	0.35	160.57	4,672.91	-238.07	-229.95	330.73	0.10	-0.09	5.27

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N
Site: NBU 1022-12F4 PAD
Well: NBU 1022-12K1BS
Wellbore: OH
Design: OH

Local Co-ordinate Reference: Well NBU 1022-12K1BS
TVD Reference: GL 5198 & KB 19 @ 5217.00ft (PIONEER 54)
MD Reference: GL 5198 & KB 19 @ 5217.00ft (PIONEER 54)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,789.00	0.70	184.04	4,766.90	-238.91	-229.89	331.27	0.43	0.37	24.97
4,884.00	0.83	175.54	4,861.90	-240.18	-229.88	332.14	0.18	0.14	-8.95
4,979.00	1.23	179.91	4,956.88	-241.88	-229.82	333.28	0.43	0.42	4.60
5,074.00	0.87	28.54	5,051.87	-242.27	-229.48	333.30	2.14	-0.38	-159.34
5,169.00	1.86	338.39	5,146.85	-240.20	-229.70	332.03	1.54	1.04	-52.79
5,264.00	1.60	343.78	5,241.80	-237.49	-230.64	330.83	0.32	-0.27	5.67
5,359.00	1.17	332.43	5,336.78	-235.36	-231.46	329.95	0.53	-0.45	-11.95
5,453.00	0.62	337.94	5,430.77	-234.04	-232.09	329.50	0.59	-0.59	5.86
5,548.00	0.44	277.56	5,525.76	-233.51	-232.65	329.53	0.58	-0.19	-63.56
5,642.00	0.44	221.66	5,619.76	-233.74	-233.25	330.12	0.44	0.00	-59.47
5,737.00	0.53	189.75	5,714.76	-234.44	-233.56	330.84	0.30	0.09	-33.59
5,831.00	0.70	180.17	5,808.75	-235.44	-233.64	331.58	0.21	0.18	-10.19
5,927.00	0.84	172.83	5,904.74	-236.73	-233.55	332.41	0.18	0.15	-7.65
6,022.00	1.14	161.98	5,999.73	-238.32	-233.17	333.23	0.37	0.32	-11.42
6,117.00	0.35	136.23	6,094.72	-239.43	-232.68	333.64	0.88	-0.83	-27.11
6,212.00	1.32	10.19	6,189.71	-238.56	-232.28	332.76	1.63	1.02	-132.67
6,306.00	1.32	19.77	6,283.69	-236.47	-231.73	330.92	0.23	0.00	10.19
6,401.00	0.97	22.94	6,378.67	-234.70	-231.04	329.20	0.37	-0.37	3.34
6,496.00	0.70	48.95	6,473.66	-233.58	-230.29	327.88	0.48	-0.28	27.38
6,591.00	0.70	106.08	6,568.65	-233.36	-229.30	327.01	0.70	0.00	60.14
6,685.00	0.70	110.21	6,662.64	-233.72	-228.21	326.47	0.05	0.00	4.39
6,780.00	0.44	28.74	6,757.64	-233.60	-227.49	325.86	0.81	-0.27	-85.76
6,875.00	1.23	351.47	6,852.63	-232.27	-227.46	324.93	0.97	0.83	-39.23
6,970.00	0.88	351.30	6,947.61	-230.54	-227.72	323.92	0.37	-0.37	-0.18
7,065.00	0.26	84.02	7,042.61	-229.80	-227.62	323.33	0.98	-0.65	97.60
7,159.00	0.62	132.19	7,136.61	-230.12	-227.03	323.13	0.52	0.38	51.24
7,254.00	0.62	123.84	7,231.60	-230.75	-226.22	322.98	0.10	0.00	-8.79
7,349.00	0.88	127.62	7,326.59	-231.48	-225.22	322.76	0.28	0.27	3.98
7,444.00	1.23	127.00	7,421.58	-232.54	-223.83	322.49	0.37	0.37	-0.65
7,539.00	1.41	136.58	7,516.55	-234.00	-222.21	322.33	0.30	0.19	10.08
7,633.00	2.02	149.50	7,610.51	-236.27	-220.57	322.72	0.76	0.65	13.74
7,728.00	2.29	148.53	7,705.44	-239.33	-218.73	323.50	0.29	0.28	-1.02
7,823.00	0.35	116.01	7,800.41	-241.08	-217.48	323.81	2.11	-2.04	-34.23
7,918.00	0.79	116.19	7,895.41	-241.49	-216.63	323.48	0.46	0.46	0.19
8,012.00	0.97	115.24	7,989.40	-242.12	-215.33	322.97	0.19	0.19	-1.01
8,107.00	0.97	137.02	8,084.39	-243.05	-214.06	322.70	0.39	0.00	22.93
8,202.00	0.93	144.27	8,179.37	-244.26	-213.06	322.81	0.13	-0.04	7.63
8,297.00	0.88	141.59	8,274.36	-245.46	-212.15	322.99	0.07	-0.05	-2.82
8,392.00	1.41	180.88	8,369.34	-247.20	-211.72	323.88	0.97	0.56	41.36
8,466.00	1.58	175.87	8,443.32	-249.13	-211.66	325.17	0.29	0.23	-6.77
LAST SDI MWD PRODUCTION SURVEY									
8,522.00	1.58	175.87	8,499.30	-250.67	-211.55	326.15	0.00	0.00	0.00
SDI PROJECTION TO BIT									

Company:	US ROCKIES REGION PLANNING	Local Co-ordinate Reference:	Well NBU 1022-12K1BS
Project:	UTAH - UTM (feet), NAD27, Zone 12N	TVD Reference:	GL 5198 & KB 19 @ 5217.00ft (PIONEER 54)
Site:	NBU 1022-12F4 PAD	MD Reference:	GL 5198 & KB 19 @ 5217.00ft (PIONEER 54)
Well:	NBU 1022-12K1BS	North Reference:	True
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	OH	Database:	EDM 5000.1 Single User Db

Design Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
238.00	238.00	0.00	0.00	FIRST SDI MWD SURFACE SURVEY
2,249.00	2,230.08	-181.20	-189.32	LAST SDI MWD SURFACE SURVEY
2,325.00	2,305.33	-188.73	-196.84	FIRST SDI MWD PRODUCTION SURVEY
8,466.00	8,443.32	-249.13	-211.66	LAST SDI MWD PRODUCTION SURVEY
8,522.00	8,499.30	-250.67	-211.55	SDI PROJECTION TO BIT

Checked By: _____ Approved By: _____ Date: _____